

ENDURING RESOURCES, LLC

425 Seventeenth Street, Suite 1500

Denver, Colorado 80202

Telephone: 303-573-1222

Facsimile: 303-573-0461

May 23, 2006

State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt lake City, Utah 84114-5801

Attention: Diana Whitney

RE: Rock House 10-23-32-30

Surface Location: NESW Sec. 30-10S-23E

2220' FSL – 2096' FWL

Lease Serial No.: UTU-81737

Bottom Hole Location: SWNE Sec. 30-10S-23E

1980' FNL – 1980' FEL

Lease Serial No.: UTU-81737

Uintah County, Utah

Dear Ms. Whitney

Attached is one copy of an application to drill for the above-referenced proposed well. This well will be drilled on federal lands.

Enduring Resources, LLC respectfully requests that this information, and future information, be held confidential.

Should you have any questions concerning this matter, please do not hesitate to call (303-350-5114).

Very truly yours

ENDURING RESOURCES, LLC



Alvin R. (Al) Arlian
Landman – Regulatory Specialist

ara/

Attachments as stated:

RECEIVED

MAY 26 2006

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO: UTU-81737	6. SURFACE: Federal
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: Enduring Resources, LLC				9. WELL NAME and NUMBER: Rock House10-23-32-30	
3. ADDRESS OF OPERATOR: 475 17th St., Ste 1500 CITY Denver STATE CO ZIP 80220				PHONE NUMBER: (303) 350-5114	
4. LOCATION OF WELL (FOOTAGES) 639251X 4419200Y 39.918749 - 109.370663 AT SURFACE: 2220' FSL - 2096' FWL NESW AT PROPOSED PRODUCING ZONE: 1980' FNL - 1980' FEL SWNE 639594X 4420127Y 39.921641 - 109.366585				10. FIELD AND POOL, OR WILDCAT: Undesignated Natural Buttes 11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESW 30 10S 23E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 79.8 miles southeast of Vernal, UT				12. COUNTY: Uintah	
13. STATE: UTAH					
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 660' BHL		16. NUMBER OF ACRES IN LEASE: 640		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 acres	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 25' Surface 1,000' BHL		19. PROPOSED DEPTH: 8,456		20. BOND DESCRIPTION: RLB0008031	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5651' KB-RT		22. APPROXIMATE DATE WORK WILL START: 8/1/2006		23. ESTIMATED DURATION: 20 days	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
20"	14"	line pipe		40	3 yards	Ready Mix	
11"	8-5/8"	J-55	24#	2,016	Premium Lead	138 sxs	3.50 11.1
					Premium Tail	138 sxs	1.15 15.8
7-7/8"	4-1/2"	N-80	11.6#	8,456	Class G	159 sxs	3.3 11.0
					50/50 Poz Class G	901 sxs	1.56 14.3

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Alvin R. (Al) Arlian TITLE Landman - Regulatory Specialist

SIGNATURE [Signature] DATE 5/22/2006

(This space for State use only)

API NUMBER ASSIGNED: 43-047-38179


(11/2001)

Federal Approval of this
Action is Necessary

Approved by the
Utah Division of
Oil, Gas and Mining
Date: 06-07-06
By: [Signature]

MAY 24 2006

ENDURING RESOURCES



1. Well footages are measured at right angles to the Section Lines.
2. The Bottom of hole bears N46°08'51"E 1608.24' from the Surface Position.
3. Bearings are based on Global Positioning Satellite observations.
4. Basis of elevation is triangulation station JEK 19 ET 1966 which is located near the South 1/4 corner of Section 8, T11S, R23E, S.L.B.&M. The elevation of this triangulation station is marked on the Archy Bench SE 7.5 min. Quadrangle as being 6054'.

REGISTERED LAND SURVEYOR
REGISTRATION No. 304251
STATE OF UTAH

38 WEST 100 NORTH. — VERNAL, UTAH 84078
(435) 789-1365

SHEET

2b

OF 11

ROCK HOUSE 10-23-32-30
(Surface Position) NAD 83 Autonomous
LATITUDE = 39° 55' 07.02"
LONGITUDE = 109° 22' 17.24"

ENDURING RESOURCES, LLC

425 Seventeenth Street, Suite 1500

Denver, Colorado 80202

Telephone: 303-573-1222

Facsimile: 303-573-0461

May 23, 2006

State of Utah
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801
Attention: Ms. Diana Whitney

RE: Exception Locations – Directional Drilled Wells
Uintah County, Utah – Federal Surface Pad

Dear Ms. Whitney:

Enduring Resources, LLC respectfully requests a spacing exception for the following wells. Four wells will be drilled from this well pad. Surface locations will be 25', more or less apart. BHL's for each well will be in its own "assigned" 40-acre, 200' drilling window. No BHL's will be within 960' of each other. All of the wells, except one vertical well on this pad are being drilled directional to limit surface impact.

<u>WELL NAME& NUMBER</u>	<u>WELL LOCATIONS</u>
a. Rock House 10-23-33-30 BHL UTU-81737	SURF 2146' FSL-2105' FWL NESW Sec 30-10S-23E BHL 1980' FSL- 1980' FEL NWSE Sec 30-10S-23E
b. Rock House 10-23-32-30 BHL UTU-81737	SURF 2220' FSL-2096' FWL NESW Sec 30-10S-23E BHL 1980' FNL- 1980' FEL SWNE Sec 30-10S-23E
c. Rock House 10-23-23-30 BHL UTU-81737	SURF 2170' FSL- 2102' FWL NESW Sec 30-10S-23E BHL SAME-VERTICAL
d. Rock House 10-23-13-30 BHL-UTU-76281	SURF 2195' FSL-2099' FWL NESW Sec 30-10S-23E BHL 1980' FSL-660' FWL SWNW Sec 30-10S-23E

Enduring Resources, LLC is the only lease owner within a 460' radius of any point of any of the well bores, the surface locations, and the four BHL's, to be drilled from this pad.

Therefore, Enduring Resources, LLC hereby grants itself permission to directionally drill the wells and the four exception well locations.

Very truly yours

ENDURING RESOURCES, LLC



Alvin R. (Al) Arlian
Landman – Regulatory Specialist

ara/

MAY 26 2006

SELF-CERTIFICATION STATEMENT

The following self-certification statement is provided per federal requirements dated June 15, 1988.

Please be advised that Enduring Resources, LLC is considered to be the operator of the following well.

Rock House 10-23-32-30

Surface Location: NESW Sec. 30-10S-23E

2220' FSL – 2096' FWL

Lease Serial No.: UTU-81737


Bottom Hole Location: SWNE Sec. 30-10S-23E

1980' FNL – 1980' FEL

Lease Serial No.: UTU-81737

Uintah County, Utah

Enduring Resources, LLC is responsible under the terms and conditions of the lease for the operations conducted upon leased lands. Bond coverage is provided by UTB000173.



Alvin R. (Al) Arlian
Regulatory Specialist
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, CO 80202
(303) 350-5114

May 22, 2006

Date

Enduring Resources, LLC

Rock House 10-23-32-30

SW-NE 30-10S-23E (Bottom Hole Location)

NE-SW 30-10S-23E (Surface Location)

Uintah County, Utah

Federal Lease: UTU-81737

ONSHORE ORDER 1 - DRILLING PLAN

1. Estimated Tops of Geological Markers:

Formation	Depth (K.B.)
Uinta	Surface
Green River	1181
Wasatch	3931
Mesaverde	5947

2. Estimated Depths of Anticipated Water, Oil, Gas or Other Minerals:

Substance	Formation	Depth (K.B.) TVD
	KB-Uinta Elevation: 5651' est.	
Oil / Gas	Green River	1181
Oil /Gas	Wasatch	3931
Oil /Gas	Mesaverde	5947
	TD	8465

An 11" hole will be drilled to approximately 2000 feet. The depth will be determined by the depth that the Birds Nest zone is encountered. The hole will be drilled 400 feet beyond the top of the Birds Nest zone and surface casing will be set.

3. Pressure Control Equipment: (3000 psi schematic attached)

- A. Type: Eleven (11) inch double gate hydraulic BOP with eleven (11) inch annular preventer on 3,000 psi casinghead, with 3,000 psi choke manifold equipped per the attached diagram. BOPE as specified in *Onshore Oil & Gas Order Number 2*. A PVT, stroke counter and flow sensor will be installed to check for flow and monitor pit volume.
- B. Pressure Rating: 3,000 psi BOPE
- C. Kelly will be equipped with upper and lower Kelly valves.
- D. Testing Procedure: Annular Preventer

At a minimum, the annular preventer will be pressure tested to 50% of the stack rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

E. Miscellaneous Information:

The blowout preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

4. Proposed Casing & Cementing Program:

A. Casing Program: All New

Hole Size	Casing Size	Wt./Ft.	Grade	Joint	Depth Set (MD)
20"	14" O.D.				40' (GL)
11"	8-5/8"	24#	J-55	ST&C	0 – 2016' (KB) est.
7-7/8"	4-1/2"	11.6#	N-80	LT&C	0 – 8456' (KB)

The surface casing will have guide shoe, 1 joint, insert float collar. Centralize the shoe joint with bowspring centralizers in the middle and top of the joint and the next 16 joints with bowspring centralizers on every other collar (8 centralizers total). Thread lock guide shoe.

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

B. Casing Design Parameters:

Depth (MD)	Casing	Collapse(psi)/SF	Burst (psi)/SF	Tension(mlbs)/SF
40' (GL)	14" OD			
2016' (KB)	8-5/8", 24#/ft, J55, STC	1370/1.52(a)	2950/3.28(b)	244/5.81(c)
8456' (KB)	4-1/2", 11.6#/ft, N-80, LTC	6350/1.44(d)	7780/1.92 (e)	223/2.64 (f)

- (a.) based on full evacuation of pipe with 8.6 ppg fluid on annulus
- (b.) based on 8.6 ppg gradient with no fluid on annulus
- (c.) based on casing string weight in 8.6 ppg mud
- (d.) based on full evacuation of pipe with 10.0 ppg fluid on annulus
- (e.) based on 9.2 ppg gradient, gas to surface, with no fluid on annulus,
no gas gradient
- (f.) based on casing string weight in 9.2 ppg mud

PROPOSED CEMENTING PROGRAM

Surface Casing (if well will circulate)-Cemented to surface

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
8-5/8"	Lead	1516	Premium cement + 16% gel + 0.25 pps celloflake	138	25%	11.1	3.50
8-5/8"	Tail	500	Premium cement + 2% CaCl ₂ + 0.25 pps celloflake	138	25%	15.8	1.15

A cement top job is required if cement fallback is greater than 10' below ground level. Top job (weight 15.8 ppg, yield 1.15 ft³/sx) cement will be premium cement w/ 3% CaCl₂ + 0.25 pps celloflake. Volume as required

Surface Casing (if well will not circulate) - Cemented to surface

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
8-5/8"	Lead	500	Premium cement + 2% CaCl ₂ + 0.25 pps celloflake	138	25	15.8	1.15
8-5/8"	Top job	As req.	Premium cement + 3% CaCl ₂ + 0.25 pps celloflake	As Req.		15.8	1.15

Production Casing and Liner - Cemented TD to 300' above base of surface casing

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft ³ /sx)
4-1/2"	Lead	1815	Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender	159	25	11.0	3.3
4-1/2"	Tail	4934	50/50 POZ Class G + 2% gel + 1% CaCl ₂ + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam	901	25	14.3	1.56

Cement volumes for the 4-1/2" Production Casing will be calculated to provide a top of cement to 300' above base of surface casing. Cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole. Actual cement types may vary due to hole conditions and cement contractor used.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

5. **Drilling Fluids (mud) Program:**

Interval (MD)	Mud Weight	Fluid Loss	Viscosity	Mud Type
0' - 2016' (KB)		No cntrl		Air/mist
2000'-3000' (KB)	8.4-8.6	No cntrl	28-36	Water
3000'-8456' (KB)	8.8-9.8	8 - 10 ml	32-42	Water/Gel

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

6. **Evaluation Program:**

Tests: No tests are currently planned.

Coring: No cores are currently planned.

Samples: No sampling is currently planned.

Logging

- Dual Induction – SFL /Gamma Ray/Caliper/SP/TDLT/CNL/ML
TD to Base Surface Casing
- Cement Bond Log / Gamma Ray:
TD to Base of Surface Casing or Top of Cement if below Base of Surface Casing

Stimulation: A stimulation or frac treatment will be designed for completion of this well based on openhole log analysis. The drill site, as approved, will be sufficient size to accommodate all completion activities.

7. **Abnormal Conditions:**

No abnormal temperatures or pressures are anticipated. No H₂S has been encountered or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 4,402 psi (calculated at 0.52 psi/foot of hole) and maximum anticipated surface pressure equals approximately 2,540 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

8. **Anticipated Starting Dates:**

- Anticipated Commencement Date- Within one year of APD issue.
- Drilling Days- Approximately 10 days
- Completion Days - Approximately 10 days
- Anticipate location construction within 30 days of permit issue.

9. **Variances:**

None anticipated

10. **Other:**

A Cultural Resource Inventory and Paleontology reconnaissance shall be conducted for the well location, access route and pipeline. The reports shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust lands Administration upon their receipt.

A measurement while drilling (MWD) system will be used to track and control the directional path of the wellbore.

ENDURING RESOURCES
Rock House 10-23-32-30
Section 30, T10S, R23E, S.L.B.&M.

FROM THE INTERSECTION OF U.S. HIGHWAY 40 AND 500 EAST STREET IN VERNAL, UTAH PROCEED IN AN EASTERLY THEN SOUTHERLY DIRECTION ALONG U.S. HIGHWAY 40 APPROXIMATELY 3.3 MILES TO THE JUNCTION OF STATE HIGHWAY 45; EXIT RIGHT AND PROCEED IN A SOUTHERLY DIRECTION ALONG STATE HIGHWAY 45 APPROXIMATELY 40.5 MILES TO THE JUNCTION OF THE DRAGON ROAD (COUNTY B ROAD 4180). THIS ROAD IS LOCATED APPROXIMATELY 4.8 MILES SOUTH OF BONANZA, UTAH. EXIT LEFT AND PROCEED IN A SOUTHEASTERLY DIRECTION ALONG COUNTY B ROAD 4180 APPROXIMATELY 4.0 MILES TO THE JUNCTION OF THE KINGS WELLS ROAD (COUNTY B ROAD 4190). EXIT RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION ALONG COUNTY B ROAD 4190 APPROXIMATELY 8.7 MILES TO THE JUNCTION OF THE ATCHEE RIDGE ROAD (COUNTY B ROAD 4270). CONTINUE ALONG COUNTY B ROAD 4190 IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 4.3 MILES TO THE JUNCTION OF THE LONG DRAW ROAD (COUNTY B ROAD 4260). CONTINUE ALONG COUNTY B ROAD 4190 IN A SOUTHERLY, THEN WESTERLY DIRECTION APPROXIMATELY 4.0 MILES TO THE JUNCTION OF COUNTY B ROAD 4160. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4160 APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THE BITTER CREEK ROAD (COUNTY B ROAD 4120). EXIT LEFT AND PROCEED IN A WESTERLY DIRECTION ALONG COUNTY B ROAD 4120 APPROXIMATELY 1.9 MILES TO THE JUNCTION OF COUNTY B ROAD 4230. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4230 APPROXIMATELY 0.9 MILES TO THE JUNCTION OF THE ATCHEES WASH ROAD (COUNTY B ROAD 4240). EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4240 APPROXIMATELY 2.7 MILES TO A CLASS D COUNTY ROAD. EXIT LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 1.4 MILES TO THE SADDLETREE DRAW ROAD (COUNTY B ROAD 4230); EXIT RIGHT AND PROCEED IN A NORTHELY DIRECTION ALONG COUNTY B ROAD 4230 APPROXIMATELY 2.1 MILES TO A CLASS D COUNTY ROAD; EXIT LEFT AND PROCEED IN AN SOUTHWESTERLY DIRECTION ALONG THE COUNTY D ROAD APPROXIMATELY 1.7 MILES TO A SECOND CLASS D COUNTY ROAD. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG THE SECOND CLASS D ROAD APPROXIMATELY 2.0 MILES TO THE PROPOSED ACCESS ROAD FOR ROCK HOUSE 10-23-21-30. FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE PROPOSED ACCESS ROAD. FOLLOW ROAD FLAGS IN A NORTHWESTERLY DIRECTION APPROXIMATELY 130 FEET TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 79.8 MILES IN A SOUTHEASTERLY DIRECTION.

Enduring Resources, LLC
Rock House 10-23-32-30
SWNE 30-10S-23E (Bottom Hole Location)
NESW 30-10S-23E (Surface Location)
Uintah County, Utah

Federal Lease: UTU-81737

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Directions to the Rock House 10-23-33-30 Rock House 10-23-32-30 Rock House 10-23-23-30 and Rock House 10-23-13-30 Wells' Pad (four-well pad).

FROM THE INTERSECTION OF U.S. HIGHWAY 40 AND 500 EAST STREET IN VERNAL, UTAH PROCEED IN AN EASTERLY THEN SOUTHERLY DIRECTION ALONG U.S. HIGHWAY 40 APPROXIMATELY 3.3 MILES TO THE JUNCTION OF STATE HIGHWAY 45; EXIT RIGHT AND PROCEED IN A SOUTHERLY DIRECTION ALONG STATE HIGHWAY 45 APPROXIMATELY 40.5 MILES TO THE JUNCTION OF THE DRAGON ROAD (COUNTY B ROAD 4180). THIS ROAD IS LOCATED APPROXIMATELY 4.8 MILES SOUTH OF BONANZA, UTAH. EXIT LEFT AND PROCEED IN A SOUTHEASTERLY DIRECTION ALONG COUNTY B ROAD 4180 APPROXIMATELY 4.0 MILES TO THE JUNCTION OF THE KINGS WELLS ROAD (COUNTY B ROAD 4190). EXIT RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION ALONG COUNTY B ROAD 4190 APPROXIMATELY 8.7 MILES TO THE JUNCTION OF THE ATCHEE RIDGE ROAD (COUNTY B ROAD 4270). CONTINUE ALONG COUNTY B ROAD 4190 IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 4.3 MILES TO THE JUNCTION OF THE LONG DRAW ROAD (COUNTY B ROAD 4260). CONTINUE ALONG COUNTY B ROAD 4190 IN A SOUTHERLY, THEN WESTERLY DIRECTION APPROXIMATELY 4.0 MILES TO THE JUNCTION OF COUNTY B ROAD 4160. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4160 APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THE BITTER CREEK ROAD (COUNTY B ROAD 4120). EXIT LEFT AND PROCEED IN A WESTERLY DIRECTION ALONG COUNTY B ROAD 4120 APPROXIMATELY 1.9 MILES TO THE JUNCTION OF COUNTY B ROAD 4230. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4230 APPROXIMATELY 0.9 MILES TO THE JUNCTION OF THE ATCHEES WASH ROAD (COUNTY B ROAD 4240). EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4240 APPROXIMATELY 2.7 MILES TO A CLASS D COUNTY ROAD. EXIT LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 1.4 MILES TO THE SADDLETREE DRAW ROAD (COUNTY B ROAD 4230); EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG COUNTY B ROAD 4230 APPROXIMATELY 2.1 MILES TO A CLASS D COUNTY ROAD; EXIT LEFT AND PROCEED IN AN SOUTHWESTERLY DIRECTION ALONG THE COUNTY D ROAD APPROXIMATELY 1.7 MILES TO A SECOND CLASS D COUNTY ROAD. EXIT RIGHT AND PROCEED IN A NORTHERLY DIRECTION ALONG THE SECOND CLASS D ROAD APPROXIMATELY 2.0 MILES TO THE PROPOSED ACCESS ROAD FOR ROCK HOUSE 10-23-21-30. FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE PROPOSED ACCESS ROAD.

FOLLOW ROAD FLAGS IN A NORTHWESTERLY DIRECTION APPROXIMATELY 130 FEET TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 79.8 MILES IN A SOUTHEASTERLY DIRECTION.

2. **Planned Access Roads:**

The proposed access road will be approximately 230 feet of new construction (ON-LEASE). Please refer to Topo Map "B" for the takeoff point for the new ON-LEASE road construction.

Access will be using County Road 4230 into section 31, then .40 of a mile of the proposed on-lease road to three other wells on this same lease. **If this well pad is drilled first then additional 0.40 of a mile of new construction will be needed.**

The proposed access road will be utilized to transport personnel, equipment and supplies to and from the proposed well site during drilling, completion and production operations. The road will be utilized year round.

The access road will be crowned 2% to 3%, ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet right-of-way. Maximum grade of road is 5% or less. Graveling or capping the roadbed will be performed as necessary to provide a well constructed, safe road. No fence crossings, culverts, turnouts, cattle guards or major cuts and fills are required. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. 1989.

The road surface and shoulders will be kept in a safe usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free flowing and will be maintained according to original construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches and the turnouts kept clear so that snowmelt will be channeled away from the road.

3. **Location of Existing Wells within a One-Mile radius (See "Topo" Map "C" attached):**

The following wells are wells located within a one (1) mile **or greater radius** of the proposed location.

- | | | |
|----|----------|---|
| a. | None: | Water Wells: |
| b. | None: | Injection Wells: |
| c. | Six: | Producing Wells: |
| | | i. Rock House 11-31 NESW Sec 31-10S-23E |
| | | ii. Rock House 12D-32 SW/4 Sec 32-10S-23E |
| | | iii. Rock House 10-23-12-32 Sec 32-10S-23E |
| | | iv. Rock House 6D-32 Sec 32-10S-23E |
| | | v. Rock House 10-23-32-32 Sec 32-10S-23E |
| | | vi. Rock House 10-23-21-32 Sec 32-10S-23E |
| d. | None: | Drilling Wells: |
| e. | None: | Shut-in Wells: |
| f. | None: | Temporarily Abandoned Wells: |
| g. | None: | Disposal Wells: |
| h. | None: | Abandoned Wells: |
| i. | None: | Dry Holes: |
| j. | None: | Observation Wells: |
| k. | Various: | Pending (staked) Wells: |
| | | Enduring has approximately 20 wells permitting in Sections 31 and 32 (many directional multi-well pad locations). |

4. **Location of Existing and/or Proposed Facilities:**

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank and be independent of the back cut.

All permanent (on site for six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the rocky Mountain Five State Inter-Agency Committee

All facilities will be painted within 6 months of installation. The color shall be Dark Olive Black. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Gas Gathering Pipeline:	ON-LEASE	270'	BLM
	OFF-LEASE	None	

If the well is capable of economic production, a surface gas gathering line and related equipment shall be installed. The surface gas gathering line shall be in use year round. A total of approximately less than 270 feet of surface gas gathering pipeline shall be laid on the surface to minimize surface disturbance:

- a. ON-LEASE approximately 270' feet, and
- b. OFF-LEASE approximately -0-.

of 4 inch or less diameter steel, unpainted, welded gas gathering line is proposed.

The proposed pipeline will begin at the well site; and tie-in directly to a proposed surface pipeline (east) adjacent to the well pad. The meter run will be housed. The gas gathering line will be buried or anchored down from the wellhead to the meter.

Upon plugging and abandonment, the gas gathering line will be removed and the disturbed area will be re-contoured and restored as near as practical to the original condition. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

5. **Location and Type of Water Supply:**

Whenever practical, water will be obtained from Enduring Resources LLC Water Right Number 49-2215 or Water Right Number 49-2216 (*See Townships of permitted Use below). If those sources are not available, a new water source shall be submitted prior to commencing operations. (These permits have one-year terms and then must be renewed)

*Enduring Water Permits' Townships of Use:

T10S-R22E	T11S-R22E	T12S-R22E
<u>T10S-R23E</u>	T11S-R23E	T12S-R23E
T10S-R24E	T11S-R24E	T12S-R24E

Water will be hauled to the location over the roads marked on "Topo" Maps "A" and "B."

No water well is to be drilled on this lease.

6 **Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized for location and access road construction.

Any gravel will be obtained from a commercial source; however, gravel sized rock debris associated with location and access road construction may be used as access road surfacing material.

7. Methods of Handling Waste Materials:

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit well be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, brake or allow discharge of liquids.

The reserve pit will be lined with ¼ felt and a minimum of 16 mm plastic with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the will be disposed of in the pit.

A chemical portable toilet will be furnished with the drilling rig. The toilet will be replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to the Vernal Wastewater Treatment Facility in accordance with state and county regulations.

Garbage, trash and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash well be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well.

Produced oil will be stored in an oil tank and then hauled by truck to a crude purchaser facility. Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to an approved disposal site.

8. Ancillary Facilities:

During drilling operations, approximately 20 days, the site will be a manned camp. Three or four additional trailers will be on location to serve as the crews' housing and eating facilities. These will be located on the perimeter of the pad site within the topsoil stockpiles. Refer to Sheet 4.

9. Well Site Layout: (Refer to Sheets #2, #3, and #4)

The attached Location Layout Diagrams described drill pad cross-sections, cuts and fills and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s) and surface material stockpiles(s).

Please see the attached diagram for rig orientation and access roads.

The top soil will be windrowed rather than piled. It will be reseeded and track walker at the time the location is constructed. Seeding will be with the determined during the onsite. (Refer to "Seed Mixture for Windrowed Top Soil Will included:" following herein.

The top soil removed from the pit area will be store separately and will not be reseeded until the pit is reclaimed.

All pits shall be fence to the following minimum standards:

- a. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- b. The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches over the new wire. Total height of the fence shall be at least 42 inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two fence posts shall be no greater than 16 feet.
- e. All wire shall be stretched by, using a stretching device, before it is attached to corner posts.
- f. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.
- g. Location size may change prior to drilling the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling, the location will be re-surveyed and a Form 9 will be submitted.

10. Plans for Surface Reclamation:**Producing Location:**

- a. Immediately upon well completion ***of the last well to be drilled from this pad***, the location and surrounding area will be cleared of all unused tubing, equipment, materials, trash and debris not required for production.
- b. Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 40CFR 3162.7.
- c. Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.
- d. The reserve pit and that portion of the location not needed for production ***(and drilling the other directional wells)*** facilities/operations will be re-contoured to the approximated natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.
- e. To prevent surface water(s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface 3 feet above surrounding round surface to allow the reclaimed pit area to drain effectively.
- f. Upon completion of back filling, leveling and re-contouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

- i. Abandoned well sites, roads and other disturbed areas will be restored as nearly as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions and re-establishment of vegetation as specified.
- ii. All disturbed surfaces will be re-contoured to the approximated natural contours with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

Seed Mixture for Windrowed Top Soil Will Included:

Indian Rice Grass 4#/s/acre
Crested Wheat Grass 4#/s/acre
Needle and Thread 4#/s/acre

Surface Ownership: Location, Access and Pipeline Route:

Wellsite: Bureau of Land Management

Access: Bureau of Land Management

Pipeline: Bureau of Land management

11. Other Information**On-site Inspection for Location, Access and Pipeline Route:**

The on-site was conducted February 9, 2006.

Attending were:

1. Doug Hammond, Enduring Resources, LLC
2. Melissa Hawk, Vernal BLM Field Office
3. Amy Torres, Vernal BLM Field Office
4. Mike Stewart, Ponderosa Construction
5. Colby Kay, Timberline Surveying

Special Conditions of Approval:

None for this well(s).

Archeology:

- a. A Cultural Resource Inventory Report is pending and to be prepared by Montgomery Archaeological Consultants.

Paleontology:

- b. A Paleontology Reconnaissance Report is pending and to be prepared by Intermountain Paleo-Consulting.

If, during operations, any archaeological or historical sites, or any objects of antiquity (subject to the Antiquities Act of June 8, 1906) are discovered, all operations which would affect such sites will be suspended and the discovery reported promptly to the surface management agency.

13, Lessee's or Operator's Representatives:**Representatives:**

Alvin R. (Al) Arlian
Landman – Regulatory Specialist
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, Colorado 80202
Office Tel: 303-350-5114
Fax Tel: 303-573-0461
aarlian@enduringresources.com

Teme Singleton
Vice President – Operations
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, Colorado 80202
Office Tel: 303-350-5711
Fax Tel: 303-573-0461
tsingleton@enduringresources.com

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his/her/its subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her/its contractor shall contact the BLM office at (435) 781-4400 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill-site and access route, that I am familiar with the conditions which presently exist, that the statements made in this plan are, to the best of my knowledge and belief, true and correct, and that the work associated with the operation proposed herein will be preformed by Enduring Resources, LLC and its contractors and subcontractors in conformity with this plan and terms and conditions with this plan and the terms and conditions under which it is approved.

Please be advised that Enduring Resources, LLC is considered to be the operator of the Rock House 0-23-32-30 Well; SW/4NE/4 (BHL) Section 30, Township 10 South, Range 23 East; Lease #:81737 Uintah County, Utah; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by BLM Statewide Oil & Gas Lease Bond No. UTB000173 and State of Utah , Division of Oil, Gas & Mining Surety Bond No. RLB0008031

ENDURING RESOURCES, LLC




Alvin R. (Al) Arlian,
Landman – Regulatory Specialist


May 23, 2006

ENDURING RESOURCES, LLC

TYPICAL 3,000 p.s.i. BLOWOUT PREVENTER SCHEMATIC



TYPICAL 3,000 p.s.i. CHOKE MANIFOLD SCHEMATIC



Weatherford International

Planning Report

Company: Enduring Resources Field: Uintah, Utah Site: NE/SW 30-10S-23E Pad Well: Rock House 10-23-32-30 Wellpath: 1	Date: 4/25/2006 Co-ordinate(NE) Reference: Well: Rock House 10-23-32-30, True North Vertical (TVD) Reference: SITE 5651.0 Section (VS) Reference: Well (0.00N,0.00E,46.15Azi) Plan: Plan #1	Time: 09:10:20 Page: 1
--	--	---

Field: Uintah, Utah Utah Central Zone U.S.A. Map System: US State Plane Coordinate System 1983 Geo Datum: GRS 1980 Sys Datum: Mean Sea Level	Map Zone: Utah, Central Zone Coordinate System: Well Centre Geomagnetic Model: igrf2005
---	--

Site: NE/SW 30-10S-23E Pad Sec. 30, T10S, R23E, Uintah County, Utah 2146 FSL & 2105 FWL Site Position: From: Geographic Position Uncertainty: 0.00 ft Ground Level: 5635.10 ft	Northing: 7146122.73 ft Easting: 2237362.92 ft Latitude: 39 55 6.280 N Longitude: 109 22 17.120 W North Reference: True
---	--

Well: Rock House 10-23-32-30 Well Position: +N/-S 74.17 ft +E/-W -9.48 ft Position Uncertainty: 0.00 ft	Slot Name: Northing: 7146196.65 ft Easting: 2237351.68 ft Latitude: 39 55 7.013 N Longitude: 109 22 17.242 W
---	---

Wellpath: 1 Current Datum: SITE Magnetic Data: 4/25/2006 Field Strength: 52871 nT Vertical Section: Depth From (TVD) ft	Height 5651.00 ft +N/-S ft	Drilled From: Surface Tie-on Depth: 0.00 ft Above System Datum: Mean Sea Level Declination: 11.66 deg Mag Dip Angle: 65.96 deg +E/-W ft	Direction deg 46.15
---	---	--	----------------------------------

Plan: Plan #1 Principal: Yes	Date Composed: 4/25/2006 Version: 1 Tied-to: From Surface
---	--

Plan Section Information

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg	Target
0.00	0.00	46.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2072.00	0.00	46.15	2072.00	0.00	0.00	0.00	0.00	0.00	0.00	
2746.94	27.00	46.15	2722.24	108.14	112.57	4.00	4.00	0.00	46.15	
5487.35	27.00	46.15	5164.01	969.96	1009.70	0.00	0.00	0.00	0.00	
6387.27	0.00	46.15	6031.00	1114.14	1159.79	3.00	-3.00	0.00	180.00	
8821.27	0.00	46.15	8465.00	1114.14	1159.79	0.00	0.00	0.00	46.15	10-23-32-30 Target

Section 1 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
0.00	0.00	46.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2000.00	0.00	46.15	2000.00	0.00	0.00	0.00	0.00	0.00	0.00	46.15
2012.00	0.00	46.15	2012.00	0.00	0.00	0.00	0.00	0.00	0.00	46.15
2072.00	0.00	46.15	2072.00	0.00	0.00	0.00	0.00	0.00	0.00	46.15

Section 2 : Start Build 4.00

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
2100.00	1.12	46.15	2100.00	0.19	0.20	0.27	4.00	4.00	0.00	0.00
2200.00	5.12	46.15	2199.83	3.96	4.12	5.72	4.00	4.00	0.00	0.00
2300.00	9.12	46.15	2299.04	12.54	13.06	18.11	4.00	4.00	0.00	0.00
2400.00	13.12	46.15	2397.14	25.90	26.96	37.39	4.00	4.00	0.00	0.00
2500.00	17.12	46.15	2493.66	43.97	45.77	63.47	4.00	4.00	0.00	0.00
2600.00	21.12	46.15	2588.12	66.66	69.39	96.22	4.00	4.00	0.00	0.00
2700.00	25.12	46.15	2680.07	93.85	97.70	135.47	4.00	4.00	0.00	0.00
2746.94	27.00	46.15	2722.24	108.14	112.57	156.10	4.00	4.00	0.00	0.00

Weatherford International

Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: NE/SW 30-10S-23E Pad
Well: Rock House 10-23-32-30
Wellpath: 1

Date: 4/25/2006 Time: 09:10:20 Page: 2
Co-ordinate(NE) Reference: Well: Rock House 10-23-32-30, True North
Vertical (TVD) Reference: SITE 5651.0
Section (VS) Reference: Well (0.00N,0.00E,46.15Azi)
Plan: Plan #1

Section 3 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
2800.00	27.00	46.15	2769.52	124.82	129.94	180.18	0.00	0.00	0.00	0.00
2900.00	27.00	46.15	2858.62	156.27	162.68	225.58	0.00	0.00	0.00	0.00
3000.00	27.00	46.15	2947.72	187.72	195.41	270.97	0.00	0.00	0.00	0.00
3100.00	27.00	46.15	3036.83	219.17	228.15	316.37	0.00	0.00	0.00	0.00
3200.00	27.00	46.15	3125.93	250.62	260.89	361.76	0.00	0.00	0.00	0.00
3300.00	27.00	46.15	3215.03	282.07	293.62	407.16	0.00	0.00	0.00	0.00
3400.00	27.00	46.15	3304.13	313.52	326.36	452.55	0.00	0.00	0.00	0.00
3500.00	27.00	46.15	3393.24	344.97	359.10	497.95	0.00	0.00	0.00	0.00
3600.00	27.00	46.15	3482.34	376.41	391.84	543.34	0.00	0.00	0.00	0.00
3700.00	27.00	46.15	3571.44	407.86	424.57	588.74	0.00	0.00	0.00	0.00
3800.00	27.00	46.15	3660.54	439.31	457.31	634.14	0.00	0.00	0.00	0.00
3900.00	27.00	46.15	3749.65	470.76	490.05	679.53	0.00	0.00	0.00	0.00
4000.00	27.00	46.15	3838.75	502.21	522.78	724.93	0.00	0.00	0.00	0.00
4100.00	27.00	46.15	3927.85	533.66	555.52	770.32	0.00	0.00	0.00	0.00
4103.53	27.00	46.15	3931.00	534.77	556.68	771.93	0.00	0.00	0.00	0.00
4200.00	27.00	46.15	4016.95	565.11	588.26	815.72	0.00	0.00	0.00	0.00
4300.00	27.00	46.15	4106.06	596.55	621.00	861.11	0.00	0.00	0.00	0.00
4400.00	27.00	46.15	4195.16	628.00	653.73	906.51	0.00	0.00	0.00	0.00
4500.00	27.00	46.15	4284.26	659.45	686.47	951.90	0.00	0.00	0.00	0.00
4600.00	27.00	46.15	4373.36	690.90	719.21	997.30	0.00	0.00	0.00	0.00
4700.00	27.00	46.15	4462.47	722.35	751.95	1042.69	0.00	0.00	0.00	0.00
4800.00	27.00	46.15	4551.57	753.80	784.68	1088.09	0.00	0.00	0.00	0.00
4900.00	27.00	46.15	4640.67	785.25	817.42	1133.48	0.00	0.00	0.00	0.00
5000.00	27.00	46.15	4729.77	816.70	850.16	1178.88	0.00	0.00	0.00	0.00
5100.00	27.00	46.15	4818.88	848.14	882.89	1224.28	0.00	0.00	0.00	0.00
5200.00	27.00	46.15	4907.98	879.59	915.63	1269.67	0.00	0.00	0.00	0.00
5300.00	27.00	46.15	4997.08	911.04	948.37	1315.07	0.00	0.00	0.00	0.00
5400.00	27.00	46.15	5086.18	942.49	981.11	1360.46	0.00	0.00	0.00	0.00
5487.35	27.00	46.15	5164.01	969.96	1009.70	1400.11	0.00	0.00	0.00	0.00

Section 4 : Start Drop -3.00

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
5500.00	26.62	46.15	5175.30	973.91	1013.82	1405.82	3.00	-3.00	0.00	180.00
5561.81	24.76	46.15	5231.00	992.48	1033.14	1432.61	3.00	-3.00	0.00	180.00
5600.00	23.62	46.15	5265.84	1003.32	1044.42	1448.26	3.00	-3.00	0.00	-180.00
5700.00	20.62	46.15	5358.47	1029.40	1071.57	1485.91	3.00	-3.00	0.00	180.00
5800.00	17.62	46.15	5452.94	1052.08	1095.19	1518.66	3.00	-3.00	0.00	180.00
5900.00	14.62	46.15	5549.00	1071.32	1115.21	1546.42	3.00	-3.00	0.00	-180.00
6000.00	11.62	46.15	5646.38	1087.04	1131.57	1569.11	3.00	-3.00	0.00	180.00
6100.00	8.62	46.15	5744.81	1099.21	1144.24	1586.68	3.00	-3.00	0.00	180.00
6200.00	5.62	46.15	5844.03	1107.79	1153.18	1599.07	3.00	-3.00	0.00	180.00
6300.00	2.62	46.15	5943.76	1112.76	1158.35	1606.25	3.00	-3.00	0.00	180.00
6303.24	2.52	46.15	5947.00	1112.86	1158.46	1606.39	3.00	-3.00	0.00	-180.00
6387.27	0.00	46.15	6031.00	1114.14	1159.79	1608.24	3.00	-3.00	0.00	180.00

Section 5 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
6400.00	0.00	46.15	6043.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
6500.00	0.00	46.15	6143.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
6600.00	0.00	46.15	6243.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
6700.00	0.00	46.15	6343.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
6800.00	0.00	46.15	6443.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
6900.00	0.00	46.15	6543.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7000.00	0.00	46.15	6643.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7100.00	0.00	46.15	6743.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7200.00	0.00	46.15	6843.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7300.00	0.00	46.15	6943.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7400.00	0.00	46.15	7043.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7500.00	0.00	46.15	7143.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7600.00	0.00	46.15	7243.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15

Weatherford International

Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: NE/SW 30-10S-23E Pad
Well: Rock House 10-23-32-30
Wellpath: 1

Date: 4/25/2006 Time: 09:10:20 Page: 3
Co-ordinate(NE) Reference: Well: Rock House 10-23-32-30, True North
Vertical (TVD) Reference: SITE 5651.0
Section (VS) Reference: Well (0.00N,0.00E,46.15Azi)
Plan: Plan #1

Section 5 : Start Hold

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	TFO deg
7700.00	0.00	46.15	7343.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7800.00	0.00	46.15	7443.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
7900.00	0.00	46.15	7543.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8000.00	0.00	46.15	7643.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8100.00	0.00	46.15	7743.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8200.00	0.00	46.15	7843.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8300.00	0.00	46.15	7943.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8400.00	0.00	46.15	8043.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8500.00	0.00	46.15	8143.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8572.27	0.00	46.15	8216.00	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8600.00	0.00	46.15	8243.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8700.00	0.00	46.15	8343.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8800.00	0.00	46.15	8443.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15
8821.27	0.00	46.15	8465.00	1114.14	1159.79	1608.24	0.00	0.00	0.00	46.15

Survey

MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	Tool/Comment
2000.00	0.00	46.15	2000.00	0.00	0.00	0.00	0.00	0.00	0.00	MWD
2012.00	0.00	46.15	2012.00	0.00	0.00	0.00	0.00	0.00	0.00	8 5/8" Surface
2072.00	0.00	46.15	2072.00	0.00	0.00	0.00	0.00	0.00	0.00	KOP
2100.00	1.12	46.15	2100.00	0.19	0.20	0.27	4.00	4.00	0.00	MWD
2200.00	5.12	46.15	2199.83	3.96	4.12	5.72	4.00	4.00	0.00	MWD
2300.00	9.12	46.15	2299.04	12.54	13.06	18.11	4.00	4.00	0.00	MWD
2400.00	13.12	46.15	2397.14	25.90	26.96	37.39	4.00	4.00	0.00	MWD
2500.00	17.12	46.15	2493.66	43.97	45.77	63.47	4.00	4.00	0.00	MWD
2600.00	21.12	46.15	2588.12	66.66	69.39	96.22	4.00	4.00	0.00	MWD
2700.00	25.12	46.15	2680.07	93.85	97.70	135.47	4.00	4.00	0.00	MWD
2746.94	27.00	46.15	2722.24	108.14	112.57	156.10	4.00	4.00	0.00	End Build
2800.00	27.00	46.15	2769.52	124.82	129.94	180.18	0.00	0.00	0.00	MWD
2900.00	27.00	46.15	2858.62	156.27	162.68	225.58	0.00	0.00	0.00	MWD
3000.00	27.00	46.15	2947.72	187.72	195.41	270.97	0.00	0.00	0.00	MWD
3100.00	27.00	46.15	3036.83	219.17	228.15	316.37	0.00	0.00	0.00	MWD
3200.00	27.00	46.15	3125.93	250.62	260.89	361.76	0.00	0.00	0.00	MWD
3300.00	27.00	46.15	3215.03	282.07	293.62	407.16	0.00	0.00	0.00	MWD
3400.00	27.00	46.15	3304.13	313.52	326.36	452.55	0.00	0.00	0.00	MWD
3500.00	27.00	46.15	3393.24	344.97	359.10	497.95	0.00	0.00	0.00	MWD
3600.00	27.00	46.15	3482.34	376.41	391.84	543.34	0.00	0.00	0.00	MWD
3700.00	27.00	46.15	3571.44	407.86	424.57	588.74	0.00	0.00	0.00	MWD
3800.00	27.00	46.15	3660.54	439.31	457.31	634.14	0.00	0.00	0.00	MWD
3900.00	27.00	46.15	3749.65	470.76	490.05	679.53	0.00	0.00	0.00	MWD
4000.00	27.00	46.15	3838.75	502.21	522.78	724.93	0.00	0.00	0.00	MWD
4100.00	27.00	46.15	3927.85	533.66	555.52	770.32	0.00	0.00	0.00	MWD
4103.53	27.00	46.15	3931.00	534.77	556.68	771.93	0.00	0.00	0.00	Wasatch
4200.00	27.00	46.15	4016.95	565.11	588.26	815.72	0.00	0.00	0.00	MWD
4300.00	27.00	46.15	4106.06	596.55	621.00	861.11	0.00	0.00	0.00	MWD
4400.00	27.00	46.15	4195.16	628.00	653.73	906.51	0.00	0.00	0.00	MWD
4500.00	27.00	46.15	4284.26	659.45	686.47	951.90	0.00	0.00	0.00	MWD
4600.00	27.00	46.15	4373.36	690.90	719.21	997.30	0.00	0.00	0.00	MWD
4700.00	27.00	46.15	4462.47	722.35	751.95	1042.69	0.00	0.00	0.00	MWD
4800.00	27.00	46.15	4551.57	753.80	784.68	1088.09	0.00	0.00	0.00	MWD
4900.00	27.00	46.15	4640.67	785.25	817.42	1133.48	0.00	0.00	0.00	MWD
5000.00	27.00	46.15	4729.77	816.70	850.16	1178.88	0.00	0.00	0.00	MWD
5100.00	27.00	46.15	4818.88	848.14	882.89	1224.28	0.00	0.00	0.00	MWD
5200.00	27.00	46.15	4907.98	879.59	915.63	1269.67	0.00	0.00	0.00	MWD
5300.00	27.00	46.15	4997.08	911.04	948.37	1315.07	0.00	0.00	0.00	MWD

Weatherford International Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: NE/SW 30-10S-23E Pad
Well: Rock House 10-23-32-30
Wellpath: 1

Date: 4/25/2006 Time: 09:10:20 Page:
Co-ordinate(NE) Reference: Well: Rock House 10-23-32-30, True North
Vertical (TVD) Reference: SITE 5651.0
Section (VS) Reference: Well (0.00N,0.00E,46.15Azi)
Plan: Plan #1

Page: 4

Survey

Survey	MD ft	Incl deg	Azim deg	TVD ft	+N/-S ft	+E/-W ft	VS ft	DLS deg/100ft	Build deg/100ft	Turn deg/100ft	Tool/Comment
5400.00	27.00	46.15	5086.18	942.49	981.11	1360.46	0.00	0.00	0.00	MWD	
5487.35	27.00	46.15	5164.01	969.96	1009.70	1400.11	0.00	0.00	0.00	Start Drop	
5500.00	26.62	46.15	5175.30	973.91	1013.82	1405.82	3.00	-3.00	0.00	MWD	
5561.81	24.76	46.15	5231.00	992.48	1033.14	1432.61	3.00	-3.00	0.00	Entry Point	
5600.00	23.62	46.15	5265.84	1003.32	1044.42	1448.26	3.00	-3.00	0.00	MWD	
5700.00	20.62	46.15	5358.47	1029.40	1071.57	1485.91	3.00	-3.00	0.00	MWD	
5800.00	17.62	46.15	5452.94	1052.08	1095.19	1518.66	3.00	-3.00	0.00	MWD	
5900.00	14.62	46.15	5549.00	1071.32	1115.21	1546.42	3.00	-3.00	0.00	MWD	
6000.00	11.62	46.15	5646.38	1087.04	1131.57	1569.11	3.00	-3.00	0.00	MWD	
6100.00	8.62	46.15	5744.81	1099.21	1144.24	1586.68	3.00	-3.00	0.00	MWD	
6200.00	5.62	46.15	5844.03	1107.79	1153.18	1599.07	3.00	-3.00	0.00	MWD	
6300.00	2.62	46.15	5943.76	1112.76	1158.35	1606.25	3.00	-3.00	0.00	MWD	
6303.24	2.52	46.15	5947.00	1112.86	1158.46	1606.39	3.00	-3.00	0.00	Mesaverde	
6387.27	0.00	46.15	6031.00	1114.14	1159.79	1608.24	3.00	-3.00	0.00	End Drop	
6400.00	0.00	46.15	6043.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
6500.00	0.00	46.15	6143.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
6600.00	0.00	46.15	6243.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
6700.00	0.00	46.15	6343.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
6800.00	0.00	46.15	6443.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
6900.00	0.00	46.15	6543.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7000.00	0.00	46.15	6643.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7100.00	0.00	46.15	6743.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7200.00	0.00	46.15	6843.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7300.00	0.00	46.15	6943.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7400.00	0.00	46.15	7043.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7500.00	0.00	46.15	7143.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7600.00	0.00	46.15	7243.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7700.00	0.00	46.15	7343.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7800.00	0.00	46.15	7443.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
7900.00	0.00	46.15	7543.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8000.00	0.00	46.15	7643.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8100.00	0.00	46.15	7743.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8200.00	0.00	46.15	7843.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8300.00	0.00	46.15	7943.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8400.00	0.00	46.15	8043.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8500.00	0.00	46.15	8143.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8572.27	0.00	46.15	8216.00	1114.14	1159.79	1608.24	0.00	0.00	0.00	Buck Tongue	
8600.00	0.00	46.15	8243.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8700.00	0.00	46.15	8343.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8800.00	0.00	46.15	8443.73	1114.14	1159.79	1608.24	0.00	0.00	0.00	MWD	
8821.27	0.00	46.15	8465.00	1114.14	1159.79	1608.24	0.00	0.00	0.00	TD	

Targets

[illegible]

Weatherford International

Planning Report

Company: Enduring Resources Field: Uintah, Utah Site: NE/SW 30-10S-23E Pad Well: Rock House 10-23-32-30 Wellpath: 1	Date: 4/25/2006 Co-ordinate(NE) Reference: Vertical (TVD) Reference: Section (VS) Reference: Plan:	Time: 09:10:20 Well: Rock House 10-23-32-30, True North SITE 5651.0 Well (0.00N,0.00E,46.15Azi) Plan #1	Page: 5
--	---	--	----------------

Casing Points

MD ft	TVD ft	Diameter in	Hole Size in	Name
2012.00	2012.00	8.625	12.250	8 5/8" Surface

Formations

MD ft	TVD ft	Formations	Lithology	Dip Angle deg	Dip Direction deg
1181.00	1181.00	Green River		0.00	0.00
4103.53	3931.00	Wasatch		0.00	0.00
6303.24	5947.00	Mesaverde		0.00	0.00
8572.27	8216.00	Buck Tongue		0.00	0.00


Annotation

MD ft	TVD ft	
2072.00	2072.00	SHL (2220 FSL & 2096 FWL)
2746.94	2722.24	KOP
5487.35	5164.01	End Build
5561.81	5231.00	Start Drop
6387.27	6031.00	Entry Point
8821.27	8465.00	End Drop
		TD

ENDURING RESOURCES

WELL PAD INTERFERENCE PLAT

ROCK HOUSE 10-23-23-30, ROCK HOUSE 10-23-32-30,
ROCK HOUSE 10-23-13-30 & ROCK HOUSE 10-23-33-30



SURFACE POSITION FOOTAGES:

ROCK HOUSE 10-23-32-30
2220' FSL & 2096' FWL

ROCK HOUSE 10-23-13-30
2195' FSL & 2099' FWL

ROCK HOUSE 10-23-23-30
2170' FSL & 2102' FWL

ROCK HOUSE 10-23-33-30
2146' FSL & 2105' FWL

BASIS OF ELEVATION IS TRIANGULATION
STATION JEK 19 ET 1966 WHICH IS
LOCATED NEAR THE SOUTH 1/4 CORNER
OF SECTION 8, T11S, R23E, S.L.B.&M.
THE ELEVATION OF THIS TRIANGULATION
STATION IS SHOWN ON THE ARCHY
BENCH SE 7.5 MIN. QUADRANGLE AS
BEING 6054'.

PROPOSED GRADED GROUND
ELEVATION OF PAD IS 5635.1'

BASIS OF BEARINGS IS THE WEST
LINE OF THE SW 1/4 OF SECTION
30, T10S, R23E, S.L.B.&M. WHICH IS
TAKEN FROM GLOBAL POSITIONING
SATELLITE OBSERVATIONS TO BEAR
N00°22'18"W.


BOTTOM HOLE FOOTAGES

ROCK HOUSE 10-23-32-30
1980' FNL & 1980' FEL

ROCK HOUSE 10-23-13-30
1980' FSL & 660' FWL

ROCK HOUSE 10-23-23-30
VERTICAL

ROCK HOUSE 10-23-33-30
1980' FSL & 1980' FEL



RELATIVE COORDINATES

From Surface Position to Bottom Hole

WELL	NORTH	EAST
32-30	1,114'	1,160'
13-30	-191'	-1,438'
23-30	VERTICAL	
33-30	-167'	1,149'

LATITUDE & LONGITUDE

Surface Position - (NAD 83) Autonomous

WELL	N. LATITUDE	W. LONGITUDE
32-30	39°55'07.02"	109°22'17.24"
13-30	39°55'06.77"	109°22'17.20"
23-30	39°55'06.53"	109°22'17.16"
33-30	39°55'06.28"	109°22'17.12"

LATITUDE & LONGITUDE

Bottom Hole - (NAD 83) Autonomous

WELL	N. LATITUDE	W. LONGITUDE
32-30	39°55'18.02"	109°22'02.36"
13-30	39°55'04.88"	109°22'35.65"
23-30	VERTICAL	
33-30	39°55'04.63"	109°22'02.37"

Section 30, T10S, R23E, S.L.B.&M.

Qtr/Qtr Location: NE SW

Footage Location: 2170' FSL & 2102' FWL

Date Surveyed:
12-21-05

Date Drawn:
12-28-05

Date Last Revision:

Surveyed By: K.R.K.

Drawn By: M.W.W.

Scale: 1" = 60'

Timberline
Land Surveying, Inc.


(435) 789-1365

38 WEST 100 NORTH VERNAL, UTAH 84078

SHEET
3
OF 11

ENDURING RESOURCES

CUT SHEET - ROCK HOUSE 10-23-23-30,
ROCK HOUSE 10-23-32-30, ROCK HOUSE 10-23-13-30
& ROCK HOUSE 10-23-33-30






CONTOUR INTERVAL = 5'


Section 30, T10S, R23E, S.L.B.&M.		Qtr/Qtr Location: NE SW	Footage Location: 2170' FSL & 2102' FWL
Date Surveyed: 12-21-05	Date Drawn: 12-28-05	Date Last Revision:	Timberline (435) 789-1365
Surveyed By: K.R.K.		Drawn By: M.W.W.	Land Surveying, Inc.
Scale: 1" = 60'		38 WEST 100 NORTH VERNAL, UTAH 84078	
			SHEET 4 OF 11

ENDURING RESOURCES

CROSS SECTIONS - ROCK HOUSE 10-23-23-30,
ROCK HOUSE 10-23-32-30, ROCK HOUSE 10-23-13-30
& ROCK HOUSE 10-23-33-30



NOTE:
UNLESS OTHERWISE NOTED
ALL CUT/FILL SLOPES ARE
AT 1.5:1



Pit overburden is included in pad cut.

REFERENCE POINTS

265' SOUTHERLY = 5637.9'
315' SOUTHERLY = 5635.1'
175' EASTERLY = 5623.3'
225' EASTERLY = 5620.1'

ESTIMATED EARTHWORK QUANTITIES (No shrink or swell adjustments have been used) (Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	7,110	8,660	Topsoil is not included in Pad Cut	-1,550
PIT	3,110	0		3,110
TOTALS	10,220	8,660	1,680	1,560


Excess Material after Pit Rehabilitation = 0 Cu. Yds.

Section 30, T10S, R23E, S.L.B.&M.		Qtr/Qtr Location: NE SW	Footage Location: 2170' FSL & 2102' FWL
Date Surveyed: 12-21-05	Date Drawn: 12-28-05	Date Last Revision:	Timberline <i>Land Surveying, Inc.</i> 38 WEST 100 NORTH VERNAL, UTAH 84078 (435) 789-1365
Surveyed By: K.R.K.	Drawn By: M.W.W.	Scale: 1" = 60'	

SHEET
5
OF 11

ENDURING RESOURCES


TYPICAL RIG LAYOUT - ROCK HOUSE 10-23-23-30,
ROCK HOUSE 10-23-32-30, ROCK HOUSE 10-23-13-30
& ROCK HOUSE 10-23-33-30




Section 30, T10S, R23E, S.L.B.&M.		Qtr/Qtr Location: NE SW	Footage Location: 2170' FSL & 2102' FWL
Date Surveyed: 12-21-05	Date Drawn: 12-28-05	Date Last Revision:	Timberline Land Surveying, Inc. 38 WEST 100 NORTH VERNAL, UTAH 84078 (435) 789-1365
Surveyed By: K.R.K.	Drawn By: M.W.W.	Scale: 1" = 60'	SHEET 6 OF 11

ENDURING RESOURCES

TYPICAL PRODUCTION LAYOUT - ROCK HOUSE 10-23-23-30,
ROCK HOUSE 10-23-32-30, ROCK HOUSE 10-23-13-30
& ROCK HOUSE 10-23-33-30



Section 30, T10S, R23E, S.L.B.&M.		Qtr/Qtr Location: NE SW	Footage Location: 2170' FSL & 2102' FWL
Date Surveyed: 12-21-05	Date Drawn: 12-28-05	Date Last Revision:	(435) 789-1365
Surveyed By: K.R.K.	Drawn By: M.W.W.	Scale: 1" = 60'	Timberline Land Surveying, Inc. 38 WEST 100 NORTH VERNAL, UTAH 84078
			SHEET 7 OF 11



LEGEND

PROPOSED ACCESS ROAD
 ■■■■ = SUBJECT WELL
 ■■■■ = OTHER WELLS
 ——— = EXISTING ROAD
 ——— = EXISTING ROAD (TO BE IMPROVED)

(B-5460) = COUNTY ROAD CLASS & NUMBER

TOPOGRAPHIC MAP "A"

SCALE: 1"=10,000'

DRAWN BY: M.W.W.

DATE SURVEYED: 12-21-05

DATE DRAWN: 12-29-05

REVISED: 05-22-06


ENDURING RESOURCES

ROCK HOUSE 10-23-32-30

Other wells on this pad: Rock House 10-23-13-30,
 Rock House 10-23-23-30, Rock House 10-23-33-30
SECTION 30, T10S, R23E, S.L.B.&M.

Timberline Land Surveying, Inc.
 38 West 100 North Vernal, Utah 84078
 (435) 789-1365

SHEET
8
OF 11



LEGEND

- PROPOSED ACCESS ROAD
- = SUBJECT WELL
- = OTHER WELLS
- = EXISTING ROAD
- = EXISTING ROAD (TO BE IMPROVED)
- (B-5460) = COUNTY ROAD CLASS & NUMBER
- = LEASE LINE AND / OR PROPERTY LINE

TOPOGRAPHIC MAP "B"

SCALE: 1" = 2000'

DRAWN BY: M.W.V.

DATE SURVEYED: 12-21-05

DATE DRAWN: 12-29-05

REVISED: 05-22-06

ENDURING RESOURCES

ROCK HOUSE 10-23-32-30

Other wells on this pad: Rock House 10-23-33-30,
Rock House 10-23-13-30, Rock House 10-23-23-30
SECTION 30, T10S, R23E, S.L.B.&M.


Timberline Land Surveying, Inc.

38 West 100 North Vernal, Utah 84078
(435) 789-1365

SHEET

9

OF 11



LEGEND

- | | |
|--------------------|--------------------------------|
| ○ = DISPOSAL WELL | ○ = WATER WELL |
| ● = PRODUCING WELL | ● = ABANDONED WELL |
| ● = SHUT IN WELL | ● = TEMPORARILY ABANDONED WELL |
| ○ = PROPOSED WELL | ⊕ = ABANDONED LOCATION |

TOPOGRAPHIC MAP "C"

DATE SURVEYED: 12-21-05

DATE DRAWN: 12-29-05

SCALE: 1" = 2000'

DRAWN BY: M.W.W.


REVISED:

ENDURING RESOURCES

Rock House 10-23-32-30
SECTION 30, T10S, R23E, S.L.B.&M.
Bottom Hole: 1980' FNL & 1980' FEL

Timberline Land Surveying, Inc.
 38 West 100 North Vernal, Utah 84078
 (435) 789-1365

SHEET
10b
OF 11



APPROXIMATE PIPELINE LENGTH = 90 Feet

LEGEND

- = PROPOSED PIPELINE
- = OTHER PIPELINE
- = LEASE LINE AND / OR PROPERTY LINE
- = PROPOSED ACCESS ROAD
- = SUBJECT WELL
- = OTHER WELLS

TOPOGRAPHIC MAP "D"

DATE SURVEYED: 12-21-05

DATE DRAWN: 12-30-05

SCALE: 1" = 1000'

DRAWN BY: M.W.W.

REVISED: 05-22-06

ENDURING RESOURCES

ROCK HOUSE 10-23-32-30

Other wells on this pad: Rock House 10-23-33-30,

Rock House 10-23-13-30, Rock House 10-23-23-30

SECTION 30, T10S, R23E, S.L.B.&M.

Timberline Land Surveying, Inc.

38 West 100 North Vernal, Utah 84078
(435) 789-1365

SHEET

11

OF 11



ENDURING RESOURCES
Rock House 10-23-32-30
NE/SW, Sec. 30, T10S, R23E
Uintah County, Utah



SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.00	0.00	46.15	0.00	0.00	0.00	0.00	0.00	0.00	
2	2072.00	0.00	46.15	2072.00	0.00	0.00	0.00	0.00	0.00	KOP
3	2746.94	27.00	46.15	2722.24	108.14	112.57	4.00	46.15	156.10	End Build
4	5487.35	27.00	46.15	5164.01	969.96	1009.70	0.00	0.00	1400.11	Start Drop
5	6387.27	0.00	46.15	6031.00	1114.14	1159.79	3.00	180.00	1608.24	End Drop
6	8821.27	0.00	46.15	8465.00	1114.14	1159.79	0.00	46.15	1608.24	TD

WELL DETAILS

Name	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
Rock House 10-23-32-30	74.17	-9.48	7146196.65	2237351.68	39°55'07.013N	109°22'17.242W	N/A

FIELD DETAILS

Utah, Utah
Utah Central Zone
U.S.A.

Geodetic System: US State Plane Coordinate System 1983
Ellipsoid: GRS 1980
Zone: Utah, Central Zone
Magnetic Model: igr2005

System Datum: Mean Sea Level
Local North: True North

SITE DETAILS

NE/SW 30-10S-23E Pad
Sec. 30, T10S, R23E, Uintah County, Utah
2146 FSL & 2105 FWL

Site Centre Latitude: 39°55'06.280N
Longitude: 109°22'17.120W

Ground Level: 5635.10
Positional Uncertainty: 0.00

TARGET DETAILS



Name	TVD	+N/-S	+E/-W	Shape
10-23-32-30 Target	8465.00	1114.14	1159.79	Rectangle (400x400)

CASING DETAILS

No.	TVD	MD	Name	Size
1	2012.00	2012.00	8 5/8" Surface	8.625

FORMATION TOP DETAILS

No.	TVDPath	MDPath	Formation
1	1181.00	1181.00	Green River
2	3931.00	4103.53	Wasatch
3	5947.00	6303.24	Mesaverde
4	8216.00	8572.27	Buck Tongue






PHOTO VIEW: FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: EASTERLY



PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: NORTHWESTERLY

ENDURING RESOURCES

Rock House 10-23-23-30, Rock House 10-23-32-30,
Rock House 10-23-13-30 & Rock House 10-23-33-30
SECTION 30, T10S, R23E, S.L.B.&M.
2170' FSL & 2102' FWL

LOCATION PHOTOS

TAKEN BY: K.R.K.

DRAWN BY: M.W.W.

DATE TAKEN: 12-21-05

DATE DRAWN: 12-30-05

REVISED:

Timberline Land Surveying, Inc.
38 West 100 North Vernal, Utah 84078
(435) 789-1365

SHEET
1
OF 11

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 05/26/2006

API NO. ASSIGNED: 43-047-38179

WELL NAME: ROCK HOUSE 10-23-32-30

OPERATOR: ENDURING RESOURCES, LLC (N2750)

CONTACT: AL ARLIAN

PHONE NUMBER: 303-350-5114

PROPOSED LOCATION:

NESW 30 100S 230E

SURFACE: 2220 FSL 2096 FWL

BOTTOM: 1980 FNL 1980 FEL

COUNTY: UINTAH

LATITUDE: 39.91875 LONGITUDE: -109.3707

UTM SURF EASTINGS: 639251 NORTHINGS: 4419800

FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-81737

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: MVRD

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. RLB0008031)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 49-2216)
☒ RDCC Review (Y/N)
(Date: _____)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

_____ R649-2-3.
Unit: _____
_____ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
_____ R649-3-3. Exception
_____ Drilling Unit
Board Cause No: _____
Eff Date: _____
Siting: _____
☒ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: _____

1. Emergency Approval
2. Spacing Shp

NATURAL BUTTES FIELD



SPACING: R649-3-11 / DIRECTIONAL DRILLING
















Field Status


- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- ☐ EXPLORATORY
- ☐ GAS STORAGE
- ☐ NF PP OIL
- ☐ NF SECONDARY
- ☐ PENDING
- ☒ PI OIL
- ☒ PP GAS
- ☒ PP GEOTHERML
- ☒ PP OIL
- ☐ SECONDARY
- ☐ TERMINATED

Wells Status

-  GAS INJECTION
-  GAS STORAGE
-  LOCATION ABANDONED
-  NEW LOCATION
-  PLUGGED & ABANDONED
-  PRODUCING GAS
-  PRODUCING OIL
-  SHUT-IN GAS
-  SHUT-IN OIL
-  TEMP. ABANDONED
-  TEST WELL
-  WATER INJECTION
-  WATER SUPPLY
-  WATER DISPOSAL
-  DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 6-JUNE-2006

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 05/26/2006

API NO. ASSIGNED: 43-047-38179

WELL NAME: ROCK HOUSE 10-23-32-30

OPERATOR: ENDURING RESOURCES, LLC (N2750)

PHONE NUMBER: 303-350-5114

CONTACT: AL ARLIAN

PROPOSED LOCATION:

NESW 30 100S 230E

SURFACE: 0909 FNL 1854 FWL

BOTTOM: 1981 FNL 1968 FEL

COUNTY: UINTAH

LATITUDE: 39.92464 LONGITUDE: -109.3715

UTM SURF EASTINGS: 639164 NORTHINGS: 4420453

FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-81737

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: MVRD

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

____ Plat

____ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. RLB0008031)

____ Potash (Y/N)

____ Oil Shale 190-5 (B) or 190-3 or 190-13

____ Water Permit
(No. 49-2216)

____ RDCC Review (Y/N)
(Date: _____)

____ Fee Surf Agreement (Y/N)

____ Intent to Commingle (Y/N)

LOCATION AND SITING:

____ R649-2-3.

Unit: _____

____ R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

____ R649-3-3. Exception

____ Drilling Unit

Board Cause No: _____

Eff Date: _____

Siting: _____

____ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: _____



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

June 7, 2006

Enduring Resources, LLC
475 17th St., Ste. 1500
Denver, CO 80202

Re: Rock House 10-23-32-30 Well, Surface Location 2220' FSL, 2096' FWL,
NE SW, Sec. 30, T. 10 South, R. 23 East, Bottom Location 1980' FNL,
1980' FEL, SW NE, Sec. 30, T. 10 South, R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-38179.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Enduring Resources, LLC
Well Name & Number Rock House 10-23-32-30
API Number: 43-047-38179
Lease: UTU-81737

Surface Location: NE SW Sec. 30 T. 10 South R. 23 East
Bottom Location: SW NE Sec. 30 T. 10 South R. 23 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

6. In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
Enduring Resources, LLC

3. ADDRESS OF OPERATOR:
475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202

PHONE NUMBER:
(303) 350-5719

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2220' FSL - 2096' FWL

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESW 30 10S 23E S

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Request for APD Extension
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill


FROM: 6/7/2007
TO: 6/7/2008

Approved by the
Utah Division of
Oil, Gas and Mining

RECEIVED

JUN 06 2007

DIV. OF OIL, GAS & MINING



Date: 06-06-07
By: [Signature]

NAME (PLEASE PRINT) Evette Bissett

TITLE Regulatory Affairs Assistant

SIGNATURE

[Signature]

DATE 6/14/2007

(This space for State use only)

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738179
Well Name: Rock House 10-23-32-30
Location: 2220' FSL - 2096' FWL, NESW, Sec 30, T10S-R23E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 6/7/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

6/4/2007
Date

Title: Regulatory Affairs Assistant

Representing: Enduring Resources, LLC

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737
2. NAME OF OPERATOR: Enduring Resources, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: n/a
PHONE NUMBER: (303) 350-5719		8. WELL NAME and NUMBER: Rock House 10-23-32-30
4. LOCATION OF WELL FOOTAGES AT SURFACE: 909' FNL - 1,854' FWL BHL = 1,981' FNL - 1,968' FEL SWNE COUNTY: Uintah		9. API NUMBER: 4304738179
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESW 30 10S 23E S STATE: UTAH		10. FIELD AND POOL, OR WILDCAT: Undesignated

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 3/11/2008	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Moved Surface location and other.
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	
	<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

1. A closed loop drilling system will be used:
 - a. No reserve pit will be constructed, and
 - b. Drilling solids will be dried and land farmed on the well pad.
2. Changes to proposed drilling and cementing program for conduct pipe:
 - a. Conductor shall be drilled and cemented as set forth in the APD, however,
 - b. An additional 500' of conductor hole shall be drilled by the conductor rig.
3. Changes to proposed drilling, casing and cementing program for surface casing:
 - a. Surface casing shall be changed from 8-5/8" O.D. to 9-5/8" O.D.
 - b. The bottom 1,500' of the 2,000' of surface hole shall be drilled by the drilling rig and the directional curve (slant) shall commence at a TVD of 500' to 2,000' (bottom of surface casing),
 - c. 2,000' of 9-5/8" O.D. surface casing shall be cemented to surface.
4. There shall be no additional changes to the directional drilling plans as set forth in the APD.
5. See attached new survey:
 - a. To satisfy the BLM (Rock House EA) this well's surface location has been moved to another pad,
 - b. Surface stake moved from NESW to NENW.
 - c. BHL is unchanged.

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman - Regulatory Specialist</u>
SIGNATURE	DATE <u>3/11/2008</u>

(This space for State use only)

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

(See Instructions on Reverse Side)

**RECEIVED
MAR 13 2008**

DIV. OF OIL, GAS & MINING

ENDURING RESOURCES, LLC

425 Seventeenth Street, Suite 1500

Denver, Colorado 80202

Telephone: 303-573-1222

Facsimile: 303-573-0461

March 11, 2008

State of Utah
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801
Attention: Ms. Diana Mason

RE: Exception Location
Rock House 10-23-32-30
SHL: NENW Sec 30-10S-24E
BHL: SWNE Sec 30-10S-24E
Uintah County, Utah – Fee Surface Pad

Dear Ms. Mason:

Enduring Resources, LLC respectfully requests a spacing exception for the above-referenced well. Six wells will be drilled from this well pad. Surface locations will be from 15' to 25', more or less, apart. BHL's for each well will be in its own "assigned" 40-acre, 200' drilling window. No BHL's will be within 960' of each other. All of the wells, except one vertical well on this pad are being drilled directional to limit surface impact within the Rock House EA area.

Enduring Resources, LLC is the only lease owner within a 460' radius of any point of any of the well bores, the surface locations, and the six BHL's, to be drilled from this pad. Sheet No. 2 of the surveyor's surveys is attached.

Therefore, Enduring Resources, LLC hereby grants itself permission to directionally drill the above-referenced well and an exception well location for each of the wells on this multi-well pad.

Very truly yours

ENDURING RESOURCES, LLC



Alvin R. (Al) Arlian
Landman – Regulatory Specialist

ara/

ENDURING RESOURCES

WELL PAD INTERFERENCE PLAT

ROCK HOUSE 10-23-32-30, ROCK HOUSE 10-23-31-30, ROCK HOUSE 10-23-11-30, ROCK HOUSE 10-23-12-30, ROCK HOUSE 10-23-22-30 & ROCK HOUSE 10-23-21-30



SURFACE POSITION FOOTAGES:

ROCK HOUSE 10-23-31-30
830' FNL & 1866' FWL

ROCK HOUSE 10-23-21-30
845' FNL & 1864' FWL

ROCK HOUSE 10-23-11-30
860' FNL & 1862' FWL

ROCK HOUSE 10-23-12-30
884' FNL & 1858' FWL

ROCK HOUSE 10-23-32-30
909' FNL & 1854' FWL

ROCK HOUSE 10-23-22-30
924' FNL & 1852' FWL

RELATIVE COORDINATES

From Surface Position to Bottom Hole

WELL	NORTH	EAST
31-30	172'	1,390'
21-30	VERTICAL	
11-30	197'	-1,201'
12-30	-1,098'	-1,201'
32-30	-1,071'	1,412'
22-30	-1,056'	125'

BASIS OF BEARINGS IS THE WEST LINE OF THE SW 1/4 OF SECTION 30, T10S, R23E, S.L.B.&M. WHICH IS TAKEN FROM GLOBAL POSITIONING SATELLITE OBSERVATIONS TO BEAR N00°22'18"W.

BASIS OF ELEVATION IS TRIANGULATION STATION JEK 19 ET 1966 WHICH IS LOCATED NEAR THE SOUTH 1/4 CORNER OF SECTION 8, T11S, R23E, S.L.B.&M. THE ELEVATION OF THIS TRIANGULATION STATION IS SHOWN ON THE ARCHY BENCH SE 7.5 MIN. QUADRANGLE AS BEING 6054'.

BOTTOM HOLE FOOTAGES

ROCK HOUSE 10-23-31-30
660' FNL & 1980' FEL

ROCK HOUSE 10-23-21-30
VERTICAL


ROCK HOUSE 10-23-11-30
660' FNL & 660' FWL

ROCK HOUSE 10-23-12-30
1980' FNL & 660' FWL

ROCK HOUSE 10-23-32-30
1981' FNL & 1968' FEL

ROCK HOUSE 10-23-22-30
1980' FNL & 1980' FWL

PROPOSED GRADED GROUND
ELEVATION OF PAD IS 5533.9'



LATITUDE & LONGITUDE

Bottom Hole - (NAD 83) Autonomous

WELL	N. LATITUDE	W. LONGITUDE
31-30	39°55'31.06"	109°22'02.32"
21-30	VERTICAL	
11-30	39°55'31.02"	109°22'35.62"
12-30	39°55'17.98"	109°22'35.68"
32-30	39°55'18.01"	109°22'02.20"
22-30	39°55'18.01"	109°22'18.74"

LATITUDE & LONGITUDE

Surface Position - (NAD 83) Autonomous

WELL	N. LATITUDE	W. LONGITUDE
31-30	39°55'29.37"	109°22'20.15"
21-30	39°55'29.22"	109°22'20.18"
11-30	39°55'29.08"	109°22'20.21"
12-30	39°55'28.83"	109°22'20.26"
32-30	39°55'28.59"	109°22'20.31"
22-30	39°55'28.44"	109°22'20.34"

Section 30 T10S, R23E, S.L.B.&M.

Qtr/Qtr Location: NE NW (Surface)

Date Surveyed:
01-29-08

Date Drawn:
02-11-08

Date Last Revision:

Timberline

(435) 789-1365

SHEET

Surveyed By: K.R.K.

Drawn By: M.W.W.

Scale: 1" = 60'

Engineering & Land Surveying, Inc.

38 WEST 100 NORTH VERNAL, UTAH 84078

2
OF 10

RIGHT-OF-WAY and DAMAGE AGREEMENT

THIS AGREEMENT is made and entered into by and between, AMERICAN GILSONITE COMPANY, (hereinafter referred to as "Grantor") and ENDURING RESOURCES, LLC (hereinafter referred to as "Grantee") effective June 1, 2006

WHEREAS, Grantee desires to enter onto and cross Grantor's property located in the NENW of Section 30-10S-23E (hereinafter referred to as the "Lands") for the purpose of drilling an exploratory oil and/or gas well, directionally the Rock House 10-23-32-30 (the "Well"), Uintah County, Utah (hereinafter referred to as the "Drillsite").

NOW THEREFORE, for and in consideration of the mutual promises and covenants herein contained, and other good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged, the parties hereto agree as follows:

- I. Grantee shall pay Grantor the sum of \$1,000.00 up front payment for damages to surface of the Lands for road access to the Well. Within sixty days of completion of the Well either as a producer or a plugged and abandoned well, Grantee shall survey the new access road Grantor for any additional damage that may have occurred during drilling and completion operations. Compensation will be on a \$6,000.00 per acre cost for any damages exceeding 4.0 acres and such compensation, if due, will be paid within thirty (30) days of the surveyor's report being released. Grantee shall utilize existing access routes to the maximum extent feasible, so as to minimize surface disturbances for access to facilities.
- II. Grantee and their assigns or agents shall have the right to use a reasonable amount of access road across the Lands and shall have the right to move derricks, drilling tools, vehicles, and all other machinery and equipment necessary or incident to the re-drilling, drilling, testing completion, operation of the wells. Such activity shall be restricted to existing public roads or access roads covered by this agreement. Any roads or surface facilities may be relocated at Grantor's expense if needed due to gilsonite mining or processing in the future.
- III. This Agreement and the rights granted herein are effective and shall continue in full force and effect so long as operations are conducted on the Well. Upon execution of this Agreement, all payments due hereunder shall be paid concurrently. Operations are defined under terms of the oil and gas lease with Grantor, and under the Rules and Regulations defined by the State of Utah.
- IV. Cattle guards and gates will be constructed, if requested by Grantor, at all places where the openings go through the existing fences and gates will be kept closed at all times except when opened for passage of traffic. Also, gates shall be installed to limit access to producing wells on roads constructed by Grantee if by mutual agreement between Grantee and Grantor.
- V. If there is any fill used for roads constructed across any drainage, then culverts will be used for the free flow of water through said drainage.

- VI. If the access road departs from existing established roadways and new construction is required, topsoil will be segregated and stockpiled for replacement during reclamation activities.
- VII. It is understood that any road constructed across the said Lands shall not exceed 30 feet in total width, including the total disturbed area between the outside of each berm, without the prior approval of Grantor.
- VIII. Upon completion of any drilled pursuant hereto Well as a dry hole and the subsequent abandonment thereof, and at the request of the Grantor, and drill pads and newly constructed road will be restored and seeded within 180 days to the condition it was in prior to commencement of operations insofar as reasonably possible. Any preexisting roads, and the improvements thereto, which are constructed by Grantee, shall be left in a good and useable condition for the continued use by Grantor. Reclaimed areas will be reseeded with a wildlife mixture approved by the Utah Division of Wildlife.
- IX. In the event that the Well is completed as a producer of oil and/or gas, Grantee shall build and maintain a permanent access road in conformance with the already established county road standards for producing oil and/or gas wells including any variances granted by the county by existing roads to the Drillsite. Disturbed areas not used for production will be re-graded and seeded with an approved wildlife seed mix within 90 days unless prohibited by weather.
- X. Upon completion of the Well(s) as a well capable of oil and/or gas production, this Agreement shall continue in full force and effect and Grantee shall pay in advance to Grantor an annual access rental of \$1,000 per roadway 30-foot width, roadway for each well, on or before June 1st of each year thereafter until the subject well is plugged and abandoned and operations cease thereon.
- XI. It is expressly understood that the settlement amounts in paragraph I are only for construction of a road and drilling location and it is not a settlement for any damages to contiguous property, personal property of the Grantor or a release of any personal injuries that may be sustained by reason of the operations carried on by Grantee or its agents.
- XII. This Agreement does not cover pipeline easements and Grantee acknowledges that it must secure a separate agreement prior to laying pipeline related to production of gas or oil on Grantor's lands.
- XIII. This Agreement shall not be assigned, nor the rights of Grantee hereunder transferred in any manner without the prior written consent of Grantor, which consent shall not be unreasonably withheld.
- XIV. Grantee shall comply at its own expense with the Workman's Compensation Law of the State of Utah and shall maintain such insurance throughout the duration of this Agreement, and shall furnish Grantor prior to beginning work on the Lands evidence of such insurance and at each policy period thereafter renewal evidence that such insurance is being maintained. Grantee, with respect to its operation in connection with this Agreement, shall also purchase or provide for (1) comprehensive general public liability insurance with a combined single limit not

less than One Million Dollars (\$1,000,000) for bodily injury and property damage; and (ii) automobile insurance with a combined single limit of not less than One Million Dollars (\$1,000,000) for bodily injury or property damage. At Grantor's request, Grantee shall furnish Grantor with a certificate or certificates of insurance secured and maintained hereunder and Grantor shall be an additional insured thereon.


- XV. In the event any person or entity (including Grantor) suffers a loss of any kind or character, or death or injury, (1) as a result of a breach of this Agreement by Grantee, or its agents, contractors, or employees, or (2) as a result of Grantee or its agents, contractors or employees performing on the Drillsite or elsewhere, any action, directly or indirectly, in furtherance of a right hereunder, or (3) from any cause whatsoever while being on the Lands and the Drillsite to conduct any work or service for Grantee shall reimburse, indemnify, defend and hold harmless Grantor for any and all losses, costs, claims, liability, litigation, demands, damages and expenses (including all attorney fees) of every kind or character which Grantor may suffer or be subject to as a result of said loss or injury whether or not such losses, costs, claims, liabilities, litigation, demands, damages, and expenses (including all attorney fees) result from the condition of Grantor's premises or facilities, unless through the sole negligence of Grantor or its agents.
- XVI. Grantee shall provide Grantor with not less than forty-eight (48) hours advance notice, either by phone or in person, of Grantee's intent to enter upon the Land for the purpose of commencing operations thereon. Grantee shall conduct its operations in such a manner as to use no more Land than is reasonably necessary and shall use all reasonable efforts not to interfere with the use of the Land by any grazing permittees. All drilling fluid pits shall be fenced within ten days of end of drilling each Well as a producer or dry hole and then the pits will be reclaimed and reseeded within 180 days of the completion of the well as a producer or a dry hole. Surface structures shall be fenced, if they represent a potential hazard to livestock, by mutual agreement between Grantor and Grantee. The type of fencing to be mutually agreed upon by Grantor and Grantee. Grantee will have ten days to effect repairs or problems with fences when notified by e-mail or in writing by Grantor. Grantor can request an extension of the closure of pits beyond the 180 days from the completion of each Well if closing the pits represents a potential hazard or closing the pits at that time will not comply with the State of Utah's reclamation requirements. An extension will not be unreasonably withheld.
- XVII. Grantee shall have the right at any time, and from time to time, to remove any or all property, fixtures, equipment and materials, placed by Grantee on the Land, including the right to draw and remove casing. Within 90 days after plugging of a Well this agreement will expire and Grantee shall remove all remaining property, fixtures, equipment and materials that were placed by Grantee on the Land. Such removal shall be accomplished at Grantee's sole cost, risk and expense. If such items are not removed within 90 days, Grantor shall have the right to remove those items from the Land and bill the associated cost for such removal to Grantee.

- XVIII. This agreement restricts the Grantee's use of Grantor's lands to the sole purpose of exploration and production of oil and/or gas at this specific site. It does not grant Grantee, its contractors, or its agents the right to use the Grantor's property for any other purpose.
- XIX. All operations of Grantee hereunder which involve drilling for and producing of oil and gas, or both, or the cessation, or abandonment, of its operations shall be conducted in a good and workmanlike manner and in accordance with standard oil field practices and in accordance with all applicable federal, state and local statutes and regulations including specifically, but not by way of limitation, such laws and regulations governing the operation, maintenance and reclamation of well sites, pipelines, tank batteries, and other related facilities as may be utilized by Grantee and its operations hereunder. Grantee shall further adhere to and abide by all federal, state and local environment statutes and regulations addressing air, water, and solid waste pollution and the handling storage, storage use and disposal of hazardous substances as prescribed in the Comprehensive Environmental Response, Compensation and Liability Act of 1986, 42 U.S.C. & 9601, et seq. (CERCLA). Grantee shall provide Grantor with copies of all applications for environmental laws, governmental requests for any information pertaining to environmental issues relating to the Land or products produced therefrom or Grantee's use thereof, copies of any responses from Grantee's to said requests, and any environmental investigations, reports, or studies involving the Land or products produced therefrom or the use thereof by Grantee which from time to time, may be obtained from Grantee.
- XX. Grantee also agrees to abide by the laws of regulations of the State of Utah designed to protect gilsonite deposits, including but not limited to those specific rules set forth in the General Rules and Regulations of the Utah Board of Oil, Gas and Mining, as amended, pertaining to such matters.
- XXI. The provisions hereof shall be considered as covenants running with the Land during the life of the Agreement and all modifications thereof, and any assignment of the Agreement shall be subject to the provisions thereof.
- XXII. This Agreement shall not be terminated in whole or in part, nor Grantee held liable for damages, because of a temporary cessation of production of drilling operations due to breakdown of equipment or due to the repairing of a well or wells or because of failure to comply with any of the express provisions or implied covenants of this Agreement if such failure is the result of the exercise of governmental authority, war, armed hostilities, act of God, strike, civil disturbance, fire, explosion, flood or any other cause, including lack of market, beyond the control of Grantee.
- XXIII. Any controversy or claim, whether based in contract, tort or otherwise arising in any way out of, relating to on in connection with this Agreement (a "Dispute") shall be finally settled by arbitration conducted expeditiously in accordance with the Commercial Arbitration Rules (the "Rules") of the American Arbitration Association (the "AAA"). In the event of a conflict between this Article and the Rules, this Article shall govern. The attorney/client and work product privileges will be honored in the arbitration as though the case were being determined in a Utah state court. The arbitration shall be conducted before one independent and


impartial arbitrator selected by the AAA pursuant to the Rules. The arbitration shall be governed by the United States Arbitration Act, 9 U.S.C. 1-16, to the exclusion of any provision of Utah law inconsistent therewith and which would produce a different result, and judgment upon the award rendered by the arbitrator may be entered by any court having jurisdiction thereof. The place of arbitration shall be Salt Lake City, Utah, and the cost of the arbitration proceeding shall be borne equally by the parties to this agreement and each party shall bear its own attorney's fees, and other expenses, provided that the arbitrator may award attorney fees, filing fees, and costs to the prevailing party as the arbitrator deems reasonable and fair. The arbitrators shall determine the claims of the parties and render their final award in accordance with the substantive law of the State of Utah exclusive of its conflict of law rules. The limitations of any actions will be determined under Utah law. The arbitrator shall permit and facilitate such discovery as the arbitrator determines is appropriate in the circumstances, taking into account the needs of the parties and the desirability of making discovery expeditious and cost-effective. The arbitrator shall actively manage the proceedings as the arbitrator deems best so as to make the proceedings fair, expeditious, economical, and less burdensome than litigation. The procedures specified in this section shall be the exclusive means of resolution of Disputes between the parties, provided that either party may seek injunctive action before a court of competent jurisdiction to prevent the occurrence of irreparable harm pending resolution of a Dispute pursuant to the provisions of this section.

XXIV. This agreement constitutes the entire Agreement between the parties hereto as to the subject matters herein set forth and supersedes all prior written or oral agreements relative thereto. No change, modification, alteration or amendment to this Agreement shall be binding upon the parties hereto except as specifically expressed in writing and signed by each party agreeing to be bound thereby.

AMERICAN GILSONITE COMPANY, Grantor

By: 
Ted Stevens, General Counsel


ENDURING RESOURCES, LLC, Grantee

By: 
Alex Campbell, Vice President

ENDURING RESOURCES

WELL PAD INTERFERENCE PLAT

ROCK HOUSE 10-23-32-30, ROCK HOUSE 10-23-31-30, ROCK HOUSE 10-23-11-30, ROCK HOUSE 10-23-12-30, ROCK HOUSE 10-23-22-30 & ROCK HOUSE 10-23-21-30



SURFACE POSITION FOOTAGES:

ROCK HOUSE 10-23-31-30
830' FNL & 1866' FWL

ROCK HOUSE 10-23-21-30
845' FNL & 1864' FWL

ROCK HOUSE 10-23-11-30
860' FNL & 1862' FWL

ROCK HOUSE 10-23-12-30
884' FNL & 1858' FWL


ROCK HOUSE 10-23-32-30
909' FNL & 1854' FWL

ROCK HOUSE 10-23-22-30
924' FNL & 1852' FWL

RELATIVE COORDINATES		
From Surface Position to Bottom Hole		
WELL	NORTH	EAST
31-30	172'	1,390'
21-30	VERTICAL	
11-30	197'	-1,201'
12-30	-1,098'	-1,201'
32-30	-1,071'	1,412'
22-30	-1,056'	125'

BASIS OF BEARINGS IS THE WEST LINE OF THE SW 1/4 OF SECTION 30, T10S, R23E, S.L.B.&M. WHICH IS TAKEN FROM GLOBAL POSITIONING SATELLITE OBSERVATIONS TO BEAR N00°22'18"W.

BASIS OF ELEVATION IS TRIANGULATION STATION JEK 19 ET 1966 WHICH IS LOCATED NEAR THE SOUTH 1/4 CORNER OF SECTION 8, T11S, R23E, S.L.B.&M. THE ELEVATION OF THIS TRIANGULATION STATION IS SHOWN ON THE ARCHY BENCH SE 7.5 MIN. QUADRANGLE AS BEING 6054'.



BOTTOM HOLE FOOTAGES

ROCK HOUSE 10-23-31-30
660' FNL & 1980' FEL

ROCK HOUSE 10-23-21-30
VERTICAL

ROCK HOUSE 10-23-11-30
660' FNL & 660' FWL

ROCK HOUSE 10-23-12-30
1980' FNL & 660' FWL

ROCK HOUSE 10-23-32-30
1981' FNL & 1968' FEL

ROCK HOUSE 10-23-22-30
1980' FNL & 1980' FWL

LATITUDE & LONGITUDE		
Bottom Hole - (NAD 83) Autonomous		
WELL	N. LATITUDE	W. LONGITUDE
31-30	39°55'31.06"	109°22'02.32"
21-30	VERTICAL	
11-30	39°55'31.02"	109°22'35.62"
12-30	39°55'17.98"	109°22'35.68"
32-30	39°55'18.01"	109°22'02.20"
22-30	39°55'18.01"	109°22'18.74"

LATITUDE & LONGITUDE		
Surface Position - (NAD 83) Autonomous		
WELL	N. LATITUDE	W. LONGITUDE
31-30	39°55'29.37"	109°22'20.15"
21-30	39°55'29.22"	109°22'20.18"
11-30	39°55'29.08"	109°22'20.21"
12-30	39°55'28.83"	109°22'20.26"
32-30	39°55'28.59"	109°22'20.31"
22-30	39°55'28.44"	109°22'20.34"

Section 30 T10S, R23E, S.L.B.&M. Qtr/Qtr Location: NE NW (Surface)


Date Surveyed: 01-29-08 Date Drawn: 02-11-08 Date Last Revision:

Surveyed By: K.R.K. Drawn By: M.W.W. Scale: 1" = 60'

Timberline (435) 789-1365
Engineering & Land Surveying, Inc.
38 WEST 100 NORTH VERNAL, UTAH 84078

SHEET
2
OF 10

Other wells on this pad: ROCK HOUSE 10-23-31-30, ROCK HOUSE 10-23-11-30, ROCK HOUSE 10-23-12-30, ROCK HOUSE 10-23-22-30 & ROCK HOUSE 10-23-21-30



CONTOUR INTERVAL = 10'


3
OF 10

38 WEST 100 NORTH VERNAL, UTAH 84078

ENDURING RESOURCES

CROSS SECTIONS - ROCK HOUSE 10-23-32-30

Other wells on this pad: ROCK HOUSE 10-23-31-30, ROCK HOUSE 10-23-11-30, ROCK HOUSE 10-23-12-30, ROCK HOUSE 10-23-22-30 & ROCK HOUSE 10-23-21-30



NOTE:
UNLESS OTHERWISE NOTED
CUT SLOPES ARE AT 1:1
FILL SLOPES ARE AT 1.5:1

Pit overburden is included in pad cut.

ESTIMATED EARTHWORK QUANTITIES (No shrink or swell adjustments have been used) (Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	26,150	27,900	Topsoil is not included in Pad Cut	-1,750
PIT	3,500	0		3,500
TOTALS	29,650	27,900	1,710	1,750

Excess Material after Pit Rehabilitation = 0 Cu. Yds.

REFERENCE POINTS

290' SOUTHERLY = 5551.7'
340' SOUTHERLY = 5554.8'
175' EASTERLY = 5496.7'
235' EASTERLY = 5483.3'

Section 30, T10S, R23E, S.L.B.&M.

Qtr/Qtr Location: NE NW (Surface)

Date Surveyed:
01-29-08

Date Drawn:
02-11-08

Date Last Revision:

Surveyed By: K.R.K.

Drawn By: M.W.W.

Scale: 1" = 60'

Timberline

(435) 789-1365

Engineering & Land Surveying, Inc.

38 WEST 100 NORTH VERNAL, UTAH 84078

SHEET


4

OF 10

ENDURING RESOURCES

TYPICAL RIG LAYOUT - ROCK HOUSE 10-23-32-30

Other wells on this pad: ROCK HOUSE 10-23-31-30, ROCK HOUSE 10-23-11-30, ROCK HOUSE 10-23-12-30, ROCK HOUSE 10-23-22-30 & ROCK HOUSE 10-23-21-30



Section 30, T10S, R23E, S.L.B.&M.

Qtr/Qtr Location: NE NW (Surface)

Date Surveyed:
01-29-08

Date Drawn:
02-11-08

Date Last Revision:

Surveyed By: K.R.K.

Drawn By: M.W.W.

Scale: 1" = 60'

Timberline

(435) 789-1365

Engineering & Land Surveying, Inc.

38 WEST 100 NORTH

VERNAL, UTAH 84078

SHEET


5

OF 10

ENDURING RESOURCES

TYPICAL PRODUCTION LAYOUT – ROCK HOUSE 10-23-32-30

Other wells on this pad: ROCK HOUSE 10-23-31-30, ROCK HOUSE 10-23-11-30, ROCK HOUSE 10-23-12-30, ROCK HOUSE 10-23-22-30 & ROCK HOUSE 10-23-21-30



Section 30, T10S, R23E, S.L.B.&M. Qtr/Qtr Location: NE NW (Surface)

Date Surveyed:
01-29-08

Date Drawn:
02-11-08

Date Last Revision:

Surveyed By: K.R.K.

Drawn By: M.W.W.

Scale: 1" = 60'

Timberline

(435) 789-1365

Engineering & Land Surveying, Inc.

38 WEST 100 NORTH VERNAL, UTAH 84078

SHEET

6

OF 10



LEGEND

PROPOSED ACCESS ROAD
 --- = SUBJECT WELL
 --- = OTHER WELLS
 --- = EXISTING ROAD
 --- = EXISTING ROAD (TO BE IMPROVED)

(B-5460) = COUNTY ROAD CLASS & NUMBER

TOPOGRAPHIC MAP "A"

SCALE: 1"=10,000'

DRAWN BY: M.W.W.

DATE SURVEYED: 02-11-08

DATE DRAWN: 02-11-08

REVISED:

ENDURING RESOURCES

Rock House 10-23-32-30


Other wells on this pad: Rock House 10-23-31-30, Rock House 10-23-11-30, Rock House 10-23-12-30, Rock House 10-23-22-30 & Rock House 10-23-21-30
SECTION 30, T10S, R23E, S.L.B.&M.

Timberline

Engineering & Land Surveying, Inc.
 38 WEST 100 NORTH VERNAL, UTAH 84078

(435) 789-1365

SHEET
 7
 OF 10



LEGEND

PROPOSED ACCESS ROAD
 = SUBJECT WELL
 = OTHER WELLS
 ——— = EXISTING ROAD
 ——— = EXISTING ROAD (TO BE IMPROVED)
 (B-5460) = COUNTY ROAD CLASS & NUMBER

— = LEASE LINE AND / OR
 PROPERTY LINE

TOPOGRAPHIC MAP "B"

SCALE: 1" = 2000'

DRAWN BY: M.W.W.

DATE SURVEYED: 02-11-08

DATE DRAWN: 02-11-08

REVISED:

ENDURING RESOURCES

Rock House 10-23-32-30


Other wells on this pad: Rock House 10-23-31-30, Rock House 10-23-11-30,
 Rock House 10-23-12-30, Rock House 10-23-22-30 & Rock House 10-23-21-30
SECTION 30, T10S, R23E, S.L.B.&M.

Timberline

Engineering & Land Surveying, Inc.
 38 WEST 100 NORTH VERNAL, UTAH 84078

(435) 789-1365

SHEET
 8
 OF 10



LEGEND

- = DISPOSAL WELL
- = PRODUCING WELL
- = SHUT IN WELL
- = PROPOSED WELL
- = WATER WELL
- = ABANDONED WELL
- = TEMPORARILY ABANDONED WELL
- ⊕ = ABANDONED LOCATION

TOPOGRAPHIC MAP "C"

DATE SURVEYED: 02-11-08

DATE DRAWN: 02-11-08

SCALE: 1" = 2000'

DRAWN BY: M.W.W.

REVISED:

ENDURING RESOURCES

Rock House 10-23-32-30
SECTION 30, T10S, R23E, S.L.B.&M.
Bottom Hole:

Timberline

Engineering & Land Surveying, Inc.
38 WEST 100 NORTH VERNAL, UTAH 84078

(435) 789-1365

SHEET
9
OF 10

Proposed Surface Location:
Rock House 10-23-32-30

Proposed Access Road

PROPOSED PIPELINE

TIE-IN POINT

Existing Pipeline From:
Well Pad 11-31

PROPOSED PIPELINE			
Segment	Owner	On Lease	Length
1	BLM	No	±490'
2	BLM	No	±4,600'
3	BLM	No	±1,930'
4	BLM	No	±4,935'
5	Fee	Yes	±240'
TOTAL			±12,195'

LEGEND

- PROPOSED PIPELINE
- OTHER PIPELINE
- PROPOSED ACCESS ROAD
- SUBJECT WELL
- OTHER WELLS
- LEASE LINE AND / OR PROPERTY LINE

TOPOGRAPHIC MAP "D"

DATE SURVEYED: 02-11-08

DATE DRAWN: 02-11-08

SCALE: 1" = 2000'

DRAWN BY: M.W.W.

REVISED:

ENDURING RESOURCES

Rock House 10-23-32-30

Other wells on this pad: Rock House 10-23-21-30, Rock House 10-23-11-30,
Rock House 10-23-12-30, Rock House 10-23-22-30 & Rock House 10-23-31-30
SECTION 30, T10S, R23E, S.L.B.&M.

Timberline

Engineering & Land Surveying, Inc.
38 WEST 100 NORTH VERNAL, UTAH 84078

(435) 789-1365

SHEET
10
OF 10

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737
2. NAME OF OPERATOR: Enduring Resources, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: n/a
4. LOCATION OF WELL FOOTAGES AT SURFACE: 909' FNL - 1,854' FWL BHL = 1,981' FNL - 1,968' FEL SWNE COUNTY: Uintah		8. WELL NAME and NUMBER: Rock House 10-23-32-30
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 30 10S 23E S STATE: UTAH		9. API NUMBER: 4304738179
		10. FIELD AND POOL, OR WILDCAT: Undesignated

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 4/9/2008	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Moved Surface location again.
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

This is the only federal well on this pad that the BLM has not approved the APD, so we have moved it to the end in case we have to come back at a later date to drill it.

1. Move SHL (on pad) to accommodate, drilling order, drilling rig safely and to fit on drilling pad without expanding drilling pad.

- A. Move SHL from: NENW 909' FNL - 1,854' FWL
B. Move SHL to: NENW 904' FNL - 1,855' FWL
C. Proposed BHL remains the same and will not change.
D. See Pad Layout, "Sheet 2 of 10" attached.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 04-13-08
By: 

639165X
4420454Y
39.924649
-109.371539

NAME (PLEASE PRINT) <u>Alvin R. (Al) Arlian</u>	TITLE <u>Landman - Regulatory Specialist</u>
SIGNATURE 	DATE <u>4/9/2008</u>

(This space for State use only)

COPY SENT TO OPERATOR

Date: 4-15-2008
Initials: LS

(See Instructions on Reverse Side)

RECEIVED


APR 11 2008

DIV. OF OIL, GAS & MINING

ENDURING RESOURCES

WELL PAD INTERFERENCE PLAT

ROCK HOUSE 10-23-12-30, ROCK HOUSE 10-23-31-30, ROCK HOUSE 10-23-11-30, ROCK HOUSE 10-23-32-30, ROCK HOUSE 10-23-22-30 & ROCK HOUSE 10-23-21-30



SURFACE POSITION FOOTAGES:

ROCK HOUSE 10-23-31-30
830' FNL & 1866' FWL

ROCK HOUSE 10-23-21-30
845' FNL & 1864' FWL

ROCK HOUSE 10-23-11-30
860' FNL & 1862' FWL

ROCK HOUSE 10-23-12-30
874' FNL & 1859' FWL


ROCK HOUSE 10-23-22-30
889' FNL & 1857' FWL

ROCK HOUSE 10-23-32-30
904' FNL & 1855' FWL

RELATIVE COORDINATES From Surface Position to Bottom Hole		
WELL	NORTH	EAST
31-30	172'	1,390'
21-30	VERTICAL	
11-30	197'	-1,201'
12-30	-1,108'	-1,203'
22-30	-1,091'	119'
32-30	-1,076'	1,411'

BASIS OF BEARINGS IS THE WEST LINE OF THE SW 1/4 OF SECTION 30, T10S, R23E, S.L.B.&M. WHICH IS TAKEN FROM GLOBAL POSITIONING SATELLITE OBSERVATIONS TO BEAR N00°22'18"W.

BASIS OF ELEVATION IS TRIANGULATION STATION JEK 19 ET 1966 WHICH IS LOCATED NEAR THE SOUTH 1/4 CORNER OF SECTION 8, T11S, R23E, S.L.B.&M. THE ELEVATION OF THIS TRIANGULATION STATION IS SHOWN ON THE ARCHY BENCH SE 7.5 MIN. QUADRANGLE AS BEING 6054'.



BOTTOM HOLE FOOTAGES

ROCK HOUSE 10-23-31-30
660' FNL & 1980' FEL

ROCK HOUSE 10-23-21-30
VERTICAL

ROCK HOUSE 10-23-11-30
660' FNL & 660' FWL

ROCK HOUSE 10-23-12-30
1980' FNL & 660' FWL

ROCK HOUSE 10-23-22-30
1980' FNL & 1980' FWL

ROCK HOUSE 10-23-32-30
1981' FNL & 1968' FEL

LATITUDE & LONGITUDE Bottom Hole - (NAD 83) Autonomous		
WELL	N. LATITUDE	W. LONGITUDE
31-30	39°55'31.06"	109°22'02.32"
21-30	VERTICAL	
11-30	39°55'31.02"	109°22'35.62"
12-30	39°55'17.98"	109°22'35.68"
22-30	39°55'18.01"	109°22'18.74"
32-30	39°55'18.01"	109°22'02.20"

LATITUDE & LONGITUDE Surface Position - (NAD 83) Autonomous		
WELL	N. LATITUDE	W. LONGITUDE
31-30	39°55'29.37"	109°22'20.15"
21-30	39°55'29.22"	109°22'20.18"
11-30	39°55'29.08"	109°22'20.21"
12-30	39°55'28.93"	109°22'20.24"
22-30	39°55'28.78"	109°22'20.27"
32-30	39°55'28.64"	109°22'20.30"

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.

UTU-33433

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

BONANZA 1023-5P

9. API Well No.

4304738213

10. Field and Pool, or Exploratory Area

NATURAL BUTTES

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE – Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/SE SEC. 5, T10S, R23E 492'FSL, 460'FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other WELL SPUD
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 9 5/8" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX.

SPUD WELL LOCATION ON 04/05/2008 AT 9:30 AM.

RECEIVED
APR 15 2008

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

SHEILA UPCHEGO

Title

SENIOR LAND ADMIN SPECIALIST

Signature

Date

April 7, 2008

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737
2. NAME OF OPERATOR: Enduring Resources, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY: Denver STATE: CO ZIP: 80202		7. UNIT or CA AGREEMENT NAME: n/a
4. LOCATION OF WELL FOOTAGES AT SURFACE: 904' FNL - 1855' FWL (MOVED)		8. WELL NAME and NUMBER: Rock House 10-23-32-30
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 30 10S 23E S		9. API NUMBER: 4304738179
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Undesignated
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Request for APD Extension
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Surface location was moved to satisfy BLM.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill

FROM: 6/6/2008
TO: 6/6/2009

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 06-09-08
By: [Signature]

COPY SENT TO OPERATOR

Date: 6.10.2008
Initials: KS

NAME (PLEASE PRINT) Alvin R. (Al) Arlian	TITLE Landman - Regulatory Specialist
SIGNATURE [Signature]	DATE 6/1/2008

(This space for State use only)

RECEIVED
JUN 06 2008
DIV. OF OIL, GAS & MINING



**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738179
Well Name: Rock House 10-23-32-30
Location: 904' FSL - 1855' FWL, NENW, Sec 30, T10S-R23E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 6/7/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐



Signature

6/1/2008
Date

Title: Landman - Regulatory Specialist

Representing: Enduring Resources, LLC

RECEIVED
JUN 06 2008
DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: Enduring Resources, LLC		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202		8. WELL NAME and NUMBER: ROCK HOUSE 10-23-32-30			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0904 FNL 1855 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 30 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047381790000			
PHONE NUMBER: 303 350-5114 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: Uintah		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/9/2009 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____ </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Request APD extension term.					
Approved by the Utah Division of Oil, Gas and Mining					
Date: June 10, 2009					
By: 					
NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory			
SIGNATURE N/A	DATE 6/9/2009				

RECEIVED June 09, 2009



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047381790000

API: 43047381790000

Well Name: ROCK HOUSE 10-23-32-30

Location: 0904 FNL 1855 FWL QTR NESW SEC 30 TWNP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 6/7/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Alvin Arlian


Date: 6/9/2009

Title: Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

Date: June 10, 2009

By: 

RECEIVED June 09, 2009

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: Enduring Resources, LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202		8. WELL NAME and NUMBER: ROCK HOUSE 10-23-32-30
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0904 FNL 1855 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 30 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047381790000
PHONE NUMBER: 303 350-5114 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: Uintah		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/7/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____ </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Request an one-year extension to APD termination date.		
Approved by the Utah Division of Oil, Gas and Mining Date: June 07, 2010 By: 		
NAME (PLEASE PRINT) Alvin Arlian		PHONE NUMBER 303 350-5114
SIGNATURE N/A		TITLE Landman-Regulatory DATE 6/4/2010



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047381790000

API: 43047381790000

Well Name: ROCK HOUSE 10-23-32-30

Location: 0904 FNL 1855 FWL QTR NESW SEC 30 TWP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 6/7/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Alvin Arlian


Date: 6/4/2010

Title: Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

Date: June 07, 2010

By:

RECEIVED June 04, 2010

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: Enduring Resources, LLC		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202		8. WELL NAME and NUMBER: ROCK HOUSE 10-23-32-30			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0904 FNL 1855 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 30 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047381790000			
PHONE NUMBER: 303 350-5114 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: Uintah		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/7/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____ </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Request an one-year extension to APD termination date.					
Approved by the Utah Division of Oil, Gas and Mining					
Date: June 07, 2010					
By: 					
NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory			
SIGNATURE N/A	DATE 6/4/2010				

RECEIVED June 04, 2010



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047381790000

API: 43047381790000

Well Name: ROCK HOUSE 10-23-32-30

Location: 0904 FNL 1855 FWL QTR NESW SEC 30 TWNP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 6/7/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the
Utah Division of
Oil, Gas and Mining**

Signature: Alvin Arlian

Date: 6/4/2010

Title: Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

Date: June 07, 2010

By: 

RECEIVED June 04, 2010

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: Enduring Resources, LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 , Denver, CO, 80202		8. WELL NAME and NUMBER: ROCK HOUSE 10-23-32-30
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0904 FNL 1855 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 30 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047381790000
9. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/7/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

 Request an one-year extension to APD termination date.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 06/06/2011

By:

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A	DATE 6/3/2011	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047381790000

API: 43047381790000

Well Name: ROCK HOUSE 10-23-32-30

Location: 0904 FNL 1855 FWL QTR NESW SEC 30 TWNP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 6/7/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Alvin Arlian

Date: 6/3/2011

Title: Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

RECEIVED Jun. 03, 2011

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: Enduring Resources, LLC		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 511-16th Street, Suite 700 , Denver, CO, 80202		8. WELL NAME and NUMBER: ROCK HOUSE 10-23-32-30			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0904 FNL 1855 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 30 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047381790000			
9. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH			
STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/7/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between; align-items: flex-start;"> <div style="width: 60%;"> Request for an one-year extension to APD expiration date. </div> <div style="width: 35%; text-align: right;"> <p style="color: red; font-weight: bold;">Approved by the Utah Division of Oil, Gas and Mining</p> <p style="color: red; font-weight: bold;">Date: June 05, 2012</p> <p style="color: red; font-weight: bold;">By: </p> </div> </div>					
NAME (PLEASE PRINT) Alvin Arlian		PHONE NUMBER 303 350-5114			
SIGNATURE N/A		TITLE Landman-Regulatory			
DATE 6/1/2012					



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047381790000

API: 43047381790000

Well Name: ROCK HOUSE 10-23-32-30

Location: 0904 FNL 1855 FWL QTR NESW SEC 30 TWNP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 6/7/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Alvin Arlian

Date: 6/1/2012

Title: Landman-Regulatory Representing: ENDURING RESOURCES, LLC

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-81737
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: Enduring Resources, LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 511-16th Street, Suite 700 , Denver, CO, 80202		8. WELL NAME and NUMBER: ROCK HOUSE 10-23-32-30
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0904 FNL 1855 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 30 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047381790000
9. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 6/7/2013	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Request for an one-year extension to APD expiration date.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: June 04, 2013

By:

NAME (PLEASE PRINT) Alvin Arlian	PHONE NUMBER 303 350-5114	TITLE Landman-Regulatory
SIGNATURE N/A	DATE 6/3/2013	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047381790000

API: 43047381790000

Well Name: ROCK HOUSE 10-23-32-30

Location: 0904 FNL 1855 FWL QTR NESW SEC 30 TWNP 100S RNG 230E MER S

Company Permit Issued to: ENDURING RESOURCES, LLC

Date Original Permit Issued: 6/7/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Alvin Arlian

Date: 6/3/2013

Title: Landman-Regulatory Representing: ENDURING RESOURCES, LLC



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

June 5, 2014

Al Arlian
Enduring Resources, LLC
511-16th Street, Suite 700
Denver, CO 80202

Re: APD Rescinded – Rock House 10-23-32-30, Sec. 30 T. 10S, R. 23E
Uintah County, Utah API No. 43-047-38179

Dear Mr. Arlian:

The Application for Permit to Drill (APD) for the subject well was approved by the Division of Oil, Gas and Mining (Division) on June 7, 2006. On June 6, 2007, June 9, 2008, June 10, 2009, June 7, 2010, June 6, 2011, June 5, 2012 and June 4, 2013 the Division granted a one-year APD extension. On June 2, 2014, you requested that the division rescind the state approved APD. No drilling activity at this location has been reported to the division. Therefore, approval to drill the well is hereby rescinded, effective June 2, 2014.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

Diana Mason
Environmental Scientist

cc: Well File
Bureau of Land Management, Vernal

